

645 DURANT AVE REMODEL & ADDITION

ALL CONSTRUCTION SHALL BE IN STRICT ACCORDANCE WITH THE FOLLOWING CODES AND STANDARDS:
 CALIFORNIA BUILDING CODE, 2016 EDITION
 CALIFORNIA RESIDENTIAL CODE, 2016 EDITION
 CALIFORNIA PLUMBING CODE, 2016 EDITION
 CALIFORNIA MECHANICAL CODE, 2016 EDITION
 CALIFORNIA ELECTRICAL CODE, 2016 EDITION
 2016 CALIFORNIA REFERENCED STANDARDS CODE
 2016 CALIFORNIA ENERGY CODE
 2016 CALIFORNIA GREEN BUILDING STANDARDS CODE
 CITY OF SAN LEANDRO MUNICIPAL CODE
 COUNTY OF ALAMEDA CODES AND ORDINANCES

ALL TRADES MUST FOLLOW MANDATORY CAL GREEN REQUIREMENTS AS DETAILED IN THE INCLUDED "G" SHEETS - NO EXCEPTIONS OR EXCLUSIONS ACCEPTED.

CONTRACTOR MUST RECYCLE AND/OR SALVAGE FOR REUSE A MINIMUM OF 65 PERCENT OF THE NON-HAZARDOUS CONSTRUCTION AND DEMOLITION WASTE IN ACCORDANCE WITH SECTION 4.408.1, ON SHEET G1.0, OR MEET A MORE STRINGENT CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT ORDINANCE PERSCRIBED BY THE CITY OF SAN LEANDRO OR COUNTY OF ALAMEDA. SEE THE FOLLOWING LINK FOR INSTRUCTIONS ON HOW TO COMPLY:
[HTTPS://SANLEANDRO.ORG/DEPTS/PW/ES/CONSTRUCTION.ASP](https://sanleandro.org/depts/pw/es/construction.asp)

DESCRIPTION OF WORK:

STRIP INTERIOR TO FRAMING. INSTALL NEW ELECTRICAL WIRING. INSTALL NEW WASTE AND SUPPLY PLUMBING. INSTALL NEW HVAC SYSTEM. ADD 88 SQ FT AT THE REAR OF THE EXISTING STRUCTURE. MODIFY FRAMING AT THE INTERIOR AND INSTALL NEW FINISHES. DEMOLISH EXISTING GARAGE STRUCTURE AND CONSTRUCT A NEW CARPORT.

PROJECT DATA:

COUNTY: ALAMEDA
 APN#: 076-293-031
 YEAR BUILT: 1925
 ZONING: RS
 OCCUPANCY: R-3
 CLIMATE ZONE: 3
 TYPE OF CONSTRUCTION: V-B
 SEISMIC CATEGORY "D"
 SPRINKLERS: NO
 STORIES: 1
 BEDROOMS: (E) 3 (N) 3
 BATHROOMS: (E) 2 (N) 2.5

(E) RESIDENCE: 1,196 SQ FT
 RESIDENCE ADDITION: 201 SQ FT
 (N) LIVING AREA: 1,397 SQ FT

(E) GARAGE (TO BE DEMOLISHED) 394 SQ FT
 (N) CARPORT : 200 SQ FT
 NET CHANGE -194 SQ FT

(E) BUILDING TOTAL S.F.: 1,590 SQ FT
 (N) BUILDING TOTAL S.F.: 1,597 SQ FT
 LOT SF: 9,750 SQ FT

SHEET INDEX:

- A0.1 COVER, PROJECT DATA, INDEX
- A0.2 CODE & CONSTRUCTION NOTES
- A1.0 SITE PLANS
- A1.10 FLOOR PLANS & DEMO PLAN
- A1.11 CONSTRUCTION PLAN
- A1.3 ROOF PLAN
- A2.1 ELEVATIONS
- A2.2 CARPORT ELEVATIONS
- A5.1 DETAILS
- A6.1 DOOR & WINDOW SCHEDULE
- E1.1 ELECTRICAL PLAN
- P1.1 WASTE, VENT, & SUPPLY PLANS
- P1.2/M1.1 GAS PLAN & MECHANICAL PLAN
- T24-A TITLE 24 SHEET 1
- T24-B TITLE 24 SHEET 2
- G1.0 CAL GREEN REQUIREMENTS
- G1.1 CAL GREEN REQUIREMENTS
- S0.0 STRUCTURAL INDEX & NOTES
- S1.0 STRUCTURAL DETAILS
- S1.1 STRUCTURAL DETAILS
- S1.2 STRUCTURAL DETAILS
- S2.0 FOUNDATION PLAN
- S2.1 GROUND FLOOR FRAMING PLAN
- S2.2 ROOF FRAMING PLAN
- S3.0 STRUCTURAL DETAILS
- S4.0 RETROFIT INFORMATION PAGE 1
- S4.1 RETROFIT INFORMATION PAGE 2
- CARPOT SUBMITTAL PACKAGE

Revision History

	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:

Drawing By:

Chris Klimen

klimen@att.net


PH: 510.928.1359

Peter Christopher Klimen


DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
 EMAIL:KLIMEN@ATT.NET DATE: 00/00/00

SITE DATA
 SITE PLAN
 SHEET INDEX


A0.1




SITE PLAN
 SCALE: 3/32"=1'-0"



ASSESSORS PARCEL MAP



VICINITY MAP



LOCAL MAP

ABBREVIATIONS

&	AND	F.B.	FLAT BAR	QT	QUARRY TILE
∠	ANGLE	F.H.W.S.	FLAT HEAD WOOD SCREW	R.W.L.	RAIN WATER LEADER
○	AT	FL.	FLOOR	R.WD.	REDWOOD
?	CENTERLINE	F.D.	FLOOR DRAIN	RGR	REGISTER
⊖	DIAMETER	F.J.	FLOOR JOISTS	REINF	REINFORCE
(E)	EXISTING	F.LUOR.	FLUORESCENT	REF	REFERENCE
(N)	NEW	FT.	FOOT OR FEET	REFG.	REFRIGERATOR
⊥	PERPENDICULAR	FTG.	FOOTING	REQ.	REQUIRED
#	FOUND	FAU.	FORCED AIR UNIT	RESIL.	RESILIENT
ABV.	ABOVE	FDN.	FOUNDATION	REWD.	REDWOOD
AB	ANCHOR BOLT	FRAM'G	FRAMING	REV	REVERSE
ACOUS.	ACOUSTICAL	FLS/FS	FULL SIZE	R.	RISER/ RADIUS
A.D.	AREA DRAIN	FURR.	FURRING	RM.	ROOM
ADJ.	ADJUSTABLE	FUT.	FUTURE	R.O.	ROUGH OPENING
AFF	ABOVE FINISH FLOOR	GALV.	GALVANIZED	S.N.D.	SANITARY NAPKIN
AGOR	AGGREGATE	G.I.	GALVANIZED IRON	S.N.R.	SANITARY NAPKIN DISPENSER
AL./ALUM.	ALUMINUM	G.S.M.	GALVANIZED SHEET METAL	S.	SCHEDULE
APPROX.	APPROXIMATE	GA.	GAUGE	S.C.D.	SEAT COVER DISPENSER
ARCH.	ARCHITECT	GL.	GLASS	SECT.	SECTION
ARCH'L	ARCHITECTURAL	G.L.	GLASS	S.C.E.D.	SEE CIVIL ENGINEER DRAWINGS
ASPH.	ASPHALT	G.B.	GRAB BAR	S.E.D.	SEE ELECTRICAL DRAWINGS
AWG.	AWNING	GR.	GRADE	S.L.D.	SEE LANDSCAPE DRAWINGS
BM.	BEAM	GND.	GROUND	S.M.D.	SEE MECHANICAL DRAWINGS
BITUM.	BITUMINOUS	GFI.	GROUND FAULT INTERRUPTER	S.P.D.	SEE PLUMBING DRAWINGS
BLK.	BLOCK	GYP.	GYPSPUM BOARD	S.S.D.	SEE STRUCTURAL DRAWINGS
BLKG.	BLOCKING	GYP.BD.	GYPSPUM BOARD	S.S.X.	SERVICE SINK
BD.	BOARD	H/C	HANDICAP	SW.	SHEET
BLT.	BOLT	H.C.P.	HANDICAP/HANDICAPPED	SHT.	SHOWER
BLT.	BOLT	HDWE.	HARDWARE	SHR.	SIMILAR
BTM	BOTTOM	HDWD.	HARDWOOD	SH	SINGLE HUNG/SHELF
BLDG.	BUILDING	HGT./HT.	HEIGHT	S	SINK
CAB.	CABINET	HCT./HT.	HOLLOW CORE	SKYLT	SKYLIGHT
C.O.	CATCH OPENING	H.M.	HOLLOW METAL	SL.	SLIDING/ SLOPE
C.B.	CATCH BASIN	HORIZ.	HORIZONTAL	SD.	SMOKE DETECTOR
CPT	CARPET	H.B.	HOSE BIB	S.D.	SOAP DISPENSER
CAS	CASEMENT	H.P.	HIGH POINT	S.C.	SOLID CORE
CHLK.	CHAIN LINK	HR.	HOUR	S	SPACE
C.I.	CAST IRON	H.V.A.C.	HEATING, VENTING & AIR CONDITIONING	SPEC.	SPECIFICATION
CLKG.	CAULKING	I.D.	INSIDE DIAMETER	SQ.	SQUARE
C.J.	CEILING JOISTS	INSUL.	INSULATION	SQ.FT.	SQUARE FOOT
CLG.	CEILING	INT.	INTERIOR	SQ.INCH	SQUARE INCH
CEM.	CEMENT	I.C.B.O.	INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS	SST	STAINLESS STEEL
CTR.	CENTER	JAN.	JANITOR	STD.	STANDARD
CER.	CERAMIC	JT.	JOINT	STA.	STATION
C.T.	CERAMIC TILE	K.D.	KILN DRIED	STL.	STEEL
CLR.	CLEAR	KIT.	KITCHEN	STR.	STRUCTURAL
CLO.	CLOSET	LAB	LABORATORY	STRUC	STRUCTURE
CMU	CONCRETE MASONRY UNIT	LAV.	LAVATORY	SUSP.	SUSPENDED
COL.	COLUMN	LKR.	LOCKER	SYM.	SYMMETRICAL
COM.	COMPOSITION VINYL TILE	MB	MACHINE BOLT	TEL.	TELEPHONE
CONC./C.	CONCRETE	MFR.	MANUFACTURER	T.V.	TELEVISION
CONN.	CONNECTION	MFG	MANUFACTURING	TEMP.	TEMPERED/TEMPORARY
CONST.	CONSTRUCTION	MAX.	MAXIMUM	TERR.	TERRAZZO
CONT.	CONTINUOUS	MECH.	MECHANICAL	THK.	THICK
CORR.	CORNER	M.C.	MEDICINE CABINET	T.I.P.D.	TOILET PAPER DISPENSER
CG	CORNER GAURD	MEMB.	MEMBRANE	T.G.	TONGUE AND GROOVE
CTSK	COUNTERSINK	MET.	METAL	T.O.C.	TOP OF CURB
DEPT.	DEPARTMENT	MH.	MAN HOLE	T.O.P.	TOP OF PAVEMENT
DET.	DETAIL	MIN.	MINIMUM	T.O.S.	TOP OF SUBFLOOR/SLAB
D.F.	DOUGLAS FIR	MIR.	MIRROR	T.O.SHTG.	TOP OF SHEATHING
D/F	DRINKING FOUNTAIN	MISC.	MISCELLANEOUS	T.O.P.	TOP OF PLATE
DIAM.	DIAMETER	M.O.	MASONRY OPENING	T.O.W.	TOP OF WALL/WINDOW
DIM.	DIMENSION	MTD.	MOUNTED	T.B.	TOWEL BAR
DISP.	DISPENSER	MUL.	MULLION	TRE.	TREAD
DR.	DOOR	N.	NORTH	TYP.	TYPICAL
D.O.	DOOR OPENING	NOM.	NOMINAL	U.L.	UNDERWRITERS LABORATORY
DBL.	DOUBLE	N.L.C.	NOT IN CONTRACT	UNC	UNFINISHED
DH.	DOUBLE HUNG	N.T.S.	NOT TO SCALE	UNIFORM BUILDING CODE W/ CALIFORNIA AMENDMENTS UNLESS OTHERWISE NOTED	
DN.	DOWN	NO or #	NUMBER	U.O.N.	URINAL
DS.	DOWN SPOUT	Obs.	OBSOLETE	UR.	URINAL
D.S.P.	DRY STAND PIPE	O.F.E.	OWNER FURNISHED EQUIPMENT	V.I.F.	VERIFY IN FIELD
DWR.	DRAWER	OFF.	OFFICE	VERT.	VERTICAL
DWG'S	DRAWINGS	O.C.	ON CENTER	V.G.	VERTICAL GRAIN
E.	EAST	OPNG.	OPENING	VEST.	VESTIBULE
EA.	EACH	OPP.	OPPOSITE	VNL./V	VINYL
E.I.F.S.	EXTERIOR INSULATED FINISH SYSTEM	O.H.	OPPOSITE HAND	VCT	VINYL COMPOSITION TILE
E.J.	EXPANSION JOINT	O.D.	OUTSIDE DIAMETER (Dia)	W.	WEST/WAX
ELEC.	ELECTRICAL	O/	OVER	WCS	WAINSCOT
EP.	ELECTRICAL PANELBOARD	O.A.	OVERHALL	W.C.	WATER CLOSET
EL./ELEV	ELEVATION	OH.	OVER HANG/OVERHEAD	WH.	WATER HEATER
ELEV	ELEVATOR	PR	PAIR	WP	WATERPROOF
EMER.	EMERGENCY	PTD	PAINTED	WT.	WEIGHT
ENCL.	ENCLOSURE	P.NL	PANEL	W/	WITH
EQ.	EQUAL	P.T.D.	PAPER TOWEL DISPENSER	W/O.	WITHOUT
EQUPT.	EQUIPMENT	P.T.D./R	PAPER TOWEL DISPENSER AND RECEPTACLE COMBO	WD.	WOOD
E.W.C.	ELECTRICAL WATER COOLER	PTR.	PAPER TOWEL RECEPTACLE		
EXT.	EXPANSION	PTN.	PARTITION		
EXPO.	EXPOSED	P.D.	PLANTER DRAIN		
EXT.	EXTERIOR	PLAS.	PLASTER		
F.C.	FACE OF CONCRETE	P.LAM.	PLASTIC LAMINATE		
F.B.	FACE OF CONCRETE BLOCK	PL.	PLATE		
F.O.M.	FACE OF MULLION	PLUMB	PLUMBING		
F.D.	FLOOR DRAIN	PLYWD/PLY	PLYWOOD		
F.O.F.	FACE OF FINISH	P.P.	POINT/PRESSURE TREATED		
F.O.S.	FACE OF STUDS	P.P.	POURED IN PLACE		
F.F.	FALSE FRONT/FINISH FLOOR	PREFAB	PREFABRICATED		
FIN.	FINISH	P/L	PROPERTY LINE		
FG	FINISH GRADE	PRCST.	PRE-CAST		
F.A.	FIRE ALARM				
F.E.	FIRE EXTINGUISHER				
F.E.C.	FIRE EXTINGUISHER CAB.				
F.H.C.	FIRE HOSE CABINET				
FFRF.	FIRE PROOF				
FIX.	FIXED				
FLASH.	FLASHING				

GENERAL NOTES:

- THESE PLANS ARE FOR GENERAL CONSTRUCTION PURPOSES ONLY. THEY ARE NOT EXHAUSTIVELY DETAILED NOR FULLY SPECIFIED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY DIMENSIONS, CONDITIONS, MATERIALS, EQUIPMENT, SELECTIONS, AND TITLE 24 COMPLIANCE.
- THE CONTRACTOR SHALL VERIFY ALL SITE GRADES, EXISTING IMPROVEMENTS, PROPERTY LINES, EASEMENTS, SETBACKS, AND UTILITIES, AND REPORT WHERE DISCREPANCIES OCCUR.
- DO NOT SCALE THE DRAWINGS. DIMENSIONS ARE TO FACE OF FINISH AND ACTUAL DOOR OPENING WIDTH UNLESS OTHERWISE NOTED (U.O.N.). ALL DIMENSIONS NOTED "CLEAR" OR "CLR" ARE FOR EQUIPMENT CLEARANCES AND MUST BE STRICTLY MAINTAINED. ALL DIMENSIONS NOTED "VERIFY" OR V. I. F. ARE TO BE CHECKED BY CONTRACTOR PRIOR TO AND DURING CONSTRUCTION. DIMENSIONS TAKE PRECEDENCE OVER SCALE OF THE DRAWING; DO NOT SCALE DRAWINGS.
- MANUFACTURER'S MATERIALS, EQUIPMENT, ETC., SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATIONS AND INSTRUCTIONS (U.O.N.). THE CONTRACTOR ACKNOWLEDGES THAT THE DRAFTER SHALL NOT SUPERVISE, DIRECT, OR HAVE CONTROL OVER THE WORK NOR SHALL THE DRAFTER HAVE ANY RESPONSIBILITY FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, OR PROCEDURES SELECTED BY THE CONTRACTOR NOR THE CONTRACTOR'S SAFETY PRECAUTIONS OR PROGRAMS IN CONNECTION WITH THE WORK. THESE RIGHTS AND RESPONSIBILITIES ARE SOLELY THOSE OF THE CONTRACTOR IN ACCORDANCE WITH THESE CONTRACT DOCUMENTS.
- INSTALLATION INSTRUCTIONS FOR ALL LISTED EQUIPMENT SHALL BE PROVIDED TO THE FIELD INSPECTOR AT TIME OF INSPECTION.
- EXTERIOR WINDOWS AND DOORS SHALL MEET THE DESIGN PRESSURE RATING REQUIREMENTS OF CBC §1714.5.
- DOORS AND WINDOWS TO THE EXTERIOR SHALL BE FULLY WEATHER STRIPPED.
- LANDINGS SHALL NOT BE MORE THAN 7-3/4" LOWER THAN THRESHOLD AND MAINTAIN 1/4" INCH PER FOOT SLOPE AWAY FROM BUILDING FOR DRAINAGE.
- SLOPE ALL GRADES AWAY FROM NEW CONSTRUCTION AT 6" FOR EVERY 5'.
- ALL NEW CONSTRUCTION TO BLEND/MATCH EXISTING.
- ALL WOOD TO BE DOUGLAS FIR #2 OR BETTER, U.O.N.
- ALL CONCRETE TO BE 2,500 P.S.I. @ 28 DAYS U.O.N.
- PROVIDE FIRE DEPARTMENT ACCESS AT ALL TIMES DURING CONSTRUCTION.
- CONTRACTOR IS TO PROVIDE AND INSTALL ALL WORK SHOWN ON DRAWINGS, SUBJECT TO THE LIMITATIONS OF SCOPE OF THE BASE BID, LISTED ABOVE. THE CONTRACTOR SHALL PROVIDE MISCELLANEOUS FASTENERS, BLOCKING AND SEALANTS INCIDENTAL TO COMPLETE THE CONTRACTED WORK. THIS SHALL INCLUDE SUPPLYING AND INSTALLING NECESSARY BACKING INSIDE WALLS FOR THE INSTALLATION OF WALL HANGING ACCESSORIES WHERE INDICATED. ALL WORK SHALL BE INSTALLED AS SHOWN ON DRAWINGS, PLUMB, AND LEVEL, TRUE TO LINE AND SECURELY FASTENED OR ANCHORED.
- CONTRACTOR SHALL REVIEW ALL PLANS AND SPECIFICATIONS TO COORDINATE WITH EXISTING BUILDING CONDITIONS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BRING ANY FIELD OBSERVED CODE VIOLATIONS, OR INCORRECT EXISTING CONSTRUCTION INCLUDING APPARENT CONFLICTS BETWEEN THE EXISTING CONSTRUCTION AND THE CONTRACT DRAWINGS TO THE IMMEDIATE ATTENTION OF THE DESIGNER. DO NOT SCALE DRAWINGS, CONTACT DESIGNER FOR CLARIFICATION OF DIMENSIONS.
- CONTRACTOR SHALL MAKE EVERY REASONABLE EFFORT TO PROTECT THE POSSESSIONS OF THE OWNER THAT REMAIN IN OR ADJACENT TO THE WORK FROM LOSS OR DAMAGE. ANY PORTION OF THE PROPERTY DAMAGED BY THE CONTRACTOR OR SUBCONTRACTOR DURING THE COURSE OF THE WORK MUST BE REPAIRED AT NO ADDITIONAL COST TO THE OWNER. THE TERM "DAMAGES" SHALL INCLUDE, BUT NOT BE LIMITED TO ANY DAMAGE CAUSED BY CONTRACT OPERATION OR WORKERS DURING CONSTRUCTION TO THE OWNER'S RESIDENCE, FURNISHINGS, CLOTHING, FENCES, ADJOINING PROPERTIES OR TO PUBLIC SPACES.

PLUMBING NOTES:

- SHOWER HEADS SHALL HAVE A MAXIMUM FLOW RATE OF 1.8 GPM MEASURED AT 80 PSI AND MUST COMPLY WITH DIVISION 4.3 OF THE CALIFORNIA GREEN BUILDING STANDARDS CODE (CALGREEN) PER CPC SECTION 408.2.
- SHOWER TO BE PROVIDED WITH PRESSURE BALANCE OR THERMOSTATIC MIXING VALVE CONTROLS
- THE SIZE OF WATER CLOSETS TO BE MAXIMUM 1.28 GALLONS PER FLUSH.
- FAUCETS AT LAVATORIES SHALL HAVE A MAXIMUM WATER SUPPLY FLOW RATE OF 1.2 GPM.
- KITCHEN SINK FAUCETS SHALL HAVE A MAXIMUM FLOW RATE OF 1.8 GPM.
- PROVIDE 1-1/2" DRAIN LINE MINIMUM FROM KITCHEN. CPC 420.3
- PROVIDE A LISTED AIR GAP FOR DISHWASHER. CPC 414.3
- PROVIDE A DEDICATED GAS LINE FROM THE METER TO THE APPLIANCE.
- PROVIDE NON-REMOVABLE BACKFLOW PREVENTION DEVICE ON ALL EXTERIOR HOSE BIBS.
- MINIMUM OF 1/4" PER FOOT (2%) SLOPE FOR ALL HORIZONTAL DRAINAGE PIPING.
- SEISMIC STRAPPING FOR HOT WATER HEATER REQUIRED PER CPC SECTION 508.2.
- THE HOT WATER HEATER TEMPERATURE/PRESSURE RELIEF VALVE SHALL HAVE ATTACHED TO IT A PIPE WHICH WILL RUN OUTSIDE THE BUILDING WITH THE END OF THE PIPE BETWEEN 6 & 24 INCHES ABOVE GRADE & POINTED DOWN
- ALL NEW GAS PIPING SHALL BE SIZED TO SUPPLY SUFFICIENT GAS TO THE APPLIANCES. THE GAS PIPING SHALL BE TESTED WITH 10 LBS. OF PRESSURE FOR A MINIMUM OF 15 MINUTES.
- HOT WATER PIPING 3/4" AND GREATER SERVING A KITCHEN SHALL BE INSULATED WITH MINIMUM 1" WALL THICKNESS INSULATION.
- ALL OVEN AND STOVE GAS VALVES SHALL BE READILY ACCESSIBLE AND BE WITHIN 3'-0" OF THE APPLIANCE. CONNECTORS MAY NOT BE CONCEALED OR PASS THROUGH ANY FLOOR, WALL PARTITION, CEILING, OR APPLIANCE HOUSING CABINET.
- A 2" ACCESSIBLE PLUMBING CLEANOUT UNDER THE SINK SHALL BE REQUIRED.
- AN AIR GAP ABOVE THE SINK RIM SHALL BE INSTALLED BETWEEN THE DISHWASHER DRAINPIPE AND THE GARBAGE DISPOSAL INLET.

MECHANICAL NOTES:

- PER CMC, SECTION 502.2.1, BACK DRAFT DAMPER ARE REQUIRED ON VENTILATION SYSTEMS EXHAUSTING TO THE EXTERIOR. POINT OF EXHAUST VENT MUST BE A MINIMUM OF 3'-0" FROM A PROPERTY LINE OR OPENINGS INTO THE BUILDINGS SUCH AS DOORS, WINDOWS, OPENING SKYLIGHTS, ATTIC VENTS.
- PROVIDE EXHAUST HOOD OVER RANGE/ COOKTOP, 100 CFM MINIMUM AND IT SHALL TERMINATE OUTSIDE.
- A VERTICAL MINIMUM CLEARANCE OF 30" IS REQUIRED ABOVE A RANGE TO COMBUSTIBLES MATERIALS, AND A MINIMUM VERTICAL CLEARANCE OF 24" ABOVE THE RANGE TO THE BUILT-IN MICROWAVE OVENS IS REQUIRED. NOTE: LARGER UNITS REQUIRE GREATER CLEARANCES, REFER TO MANUFACTURER REQUIREMENTS.

ELECTRICAL NOTES:

- ARC FAULT CIRCUIT INTERRUPTER (AFCI) REQUIRED FOR ALL NEW 120-VOLT, SINGLE-PHASE, 15 AND 20 AMPERE BRANCH CIRCUITS SUPPLYING OUTLETS INSTALLED IN KITCHENS, BATHROOMS, FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, LAUNDRY ROOMS, GARAGE, HALLWAYS, OR SIMILAR ROOMS OR AREAS.
- PER CEC 406.12, PROVIDE TAMPER-RESISTANT RECEPTACLES IN AREAS SPECIFIED IN CEC 210.52, SPECIFICALLY ALL 125-VOLT, 15- AND 20-AMPERE RECEPTACLES IN AREAS SUCH AS KITCHENS, BATHROOMS, FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, SUNROOMS, BEDROOMS, RECREATION ROOMS, LAUNDRY ROOMS, GARAGE, OR SIMILAR ROOMS OR AREAS OF A DWELLING UNIT.
- RECEPTACLES SHALL BE INSTALLED SUCH THAT NO POINT MEASURED HORIZONTALLY ALONG THE FLOOR LINE OF ANY WALL SPACE IS MORE THAN 6 FEET FROM A RECEPTACLE OUTLET. THIS ALLOWS FOR A MAXIMUM OF 12 FEET BETWEEN RECEPTACLES ON THE SAME WALL.
- SMOKE ALARM.** WHEN A PERMIT IS REQUIRED FOR ALTERATIONS, REPAIRS OR ADDITIONS EXCEEDING \$1,000, EXISTING DWELLINGS THAT HAVE ATTACHED GARAGES OR FUEL BURNING APPLIANCES, SMOKE DETECTORS SHALL BE INSTALLED: (A) IN EACH SLEEPING ROOM, (B) OUTSIDE EACH SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS, (C) ON EACH STORY OF THE DWELLING, INCLUDING BASEMENTS AND HABITABLE ATTICS BUT NOT INCLUDING CRAWL SPACES AND UNINHABITABLE ATTICS. NEW SMOKE ALARMS TO BE INTERCONNECTED. SMOKE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING PROVIDED THAT SUCH WIRING IS SERVED FROM A COMMERCIAL SOURCE AND SHALL BE EQUIPPED WITH A BATTERY BACKUP. SMOKE ALARMS WITH INTEGRAL STROBES THAT ARE NOT EQUIPPED WITH BATTERY BACKUP SHALL BE CONNECTED TO AN EMERGENCY ELECTRICAL SYSTEM. SMOKE ALARMS SHALL EMIT A SIGNAL WHEN THE BATTERIES ARE LOW. WIRING SHALL BE PERMANENT AND WITHOUT A DISCONNECTING SWITCH OTHER THAN AS REQUIRED FOR OVERCURRENT PROTECTION.
- CARBON MONOXIDE ALARM.** WHEN A PERMIT IS REQUIRED FOR ALTERATIONS, REPAIRS OR ADDITIONS EXCEEDING \$1,000, EXISTING DWELLINGS THAT HAVE ATTACHED GARAGES OR FUEL BURNING APPLIANCES SHALL BE PROVIDED WITH A CARBON MONOXIDE ALARM IN THE FOLLOWING LOCATIONS: (A) OUTSIDE OF THE DWELLING UNIT SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOM(S); (B) ON EVERY LEVEL OF A DWELLING UNIT INCLUDING BASEMENTS. CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING WHERE SUCH WIRING IS SERVED FROM A COMMERCIAL SOURCE AND, WHERE PRIMARY POWER IS INTERRUPTED, SHALL RECEIVE POWER FROM A BATTERY. WIRING SHALL BE PERMANENT AND WITHOUT A DISCONNECTING SWITCH OTHER THAN THOSE REQUIRED FOR OVERCURRENT PROTECTION. COMBINATION CARBON MONOXIDE AND SMOKE ALARMS SHALL BE PERMITTED TO BE USED IN LIEU OF CARBON MONOXIDE ALARMS.
- ANY SMOKE ALARM WITHIN 20 FEET OF A PERMANENTLY INSTALLED COOKING APPLIANCE SHALL BE THE IONIZATION OR PHOTOELECTRIC ALARM TYPE AND HAVE A MINIMUM SPACING OF 10 FEET AWAY.
- THE MINIMUM DISCONNECTION MEANS FOR A SINGLE FAMILY DWELLING IS 100 AMPERES, 3-WIRE.
- PROVIDE ADEQUATE GROUND TO ELECTRICAL SERVICE ENTRY PANEL. VERIFY OR PROVIDE BOND TO METAL GAS AND WATER PIPES.
- ELECTRICAL SUB PANELS SHALL NOT BE LOCATED IN THE VICINITY OF EASILY IGNITABLE MATERIALS SUCH AS CLOTHES CLOSETS.
- STAGGER NEW ELECTRICAL OUTLETS BY AT LEAST 24-INCHES ON THE OPPOSITE SIDE OF THE FIRE-WALL (GARAGE/ HOUSE WALL) PER BUILDING CODE SECTION 712.3.2.
- PROVIDE AND INSTALL RECEPTACLE OUTLETS AT HOUSE EXTERIOR WALLS THAT ARE GFCI PROTECTED, GASKETED-COVER TYPE FOR USE IN WET LOCATIONS.
- PROVIDE AT LEAST ONE GFCI OUTLET WITHIN 3 FEET OF EACH SINK IN THE BATHROOMS.
- AT LEAST ONE NEW LUMINAIRE IN EACH BATHROOM SHALL BE CONTROLLED BY A VACANCY SENOR.
- PER CEC, AT LEAST ONE 20-AMP BRANCH CIRCUIT SHALL BE PROVIDED TO SUPPLY THE BATHROOM RECEPTACLE OUTLETS. THIS CIRCUIT SHALL HAVE NO OTHER OUTLETS.
- BATHROOM LIGHTING CANNOT BE ON AN OUTLET CIRCUIT.
- UNDER CABINET LUMINAIRES SHALL BE SEPERATELY SWITCHED
- A MINIMUM OF (2) 20 AMP GFCI PROTECTED CIRCUITS SHALL SUPPLY ALL KITCHEN COUNTER TOP RECEPTACLES, CEC 210.11 (C)(2), & (C) (3).
- PROVIDE 20 AMP DEDICATED CIRCUITS FOR THE DISHWASHER, GARBAGE DISPOSAL, REFRIGERATOR, MICROWAVE AND RANGE
- RECEPTACLE OUTLETS SHALL BE LOCATED NO MORE THAN 20" ABOVE COUNTER TOP AND NO MORE THAN 12" BELOW IF COUNTER DOES NOT EXTEND MORE THAN 6" FROM BASE. PENINSULA COUNTERTOP SPACES 24" LONG OR GREATER AND SHORT DIMENSION 12" OR GREATER SHALL HAVE AT LEAST ONE RECEPTACLE.
- ALL KITCHEN RECEPTACLES SHALL BE GFCI PROTECTED. CEC 210(A) 5 & 6.
- THE KITCHEN COUNTERTOP WALLS SHALL BE NO MORE THAN 24" FROM A GFCI OUTLET. THIS DOES NOT APPLY TO ANY COUNTERTOP WALLS BEHIND SINKS, RANGES OR MOUNTED COOKTOPS.
- THE UNDERCOUNTER ELECTRICAL OUTLET SERVING THE DISHWASHER SHALL BE GFCI PROTECTED. MULTI-WIRE DUPLEX RECEPTACLES FOR GARBAGE DISPOSALS & DISHWASHERS REQUIRE A COMMON TRIP BREAKER IN THE SERVICE PANELS.
- THE MAXIMUM LENGTH FOR A GARBAGE DISPOSAL CORD IS 36" AND A DISHWASHER IS 48". ATTACHMENT PLUG AND RECEPTACLE SHALL BE ACCESSIBLE AND LABELED.
- ISLANDS OR PENINSULAS REQUIRE AT LEAST 1 RECEPTACLE. RECEPTACLES MAY NOT BE MORE THAN 12" BELOW THE COUNTER SURFACE OR BE BELOW A COUNTER THAT EXTENDS MORE THAN 6" BEYOND A CABINET'S END.
- A MINIMUM OF 3'-0" CLEARANCE IS REQUIRED BETWEEN THE COUNTER FRONTS AND APPLIANCES, OR COUNTER FRONTS AND WALLS.
- DIMMERS OR VACANCY SENSORS ARE REQUIRED TO CONTROL ALL HIGH-EFFICACY LUMINAIRES, EXCEPT CLOSETS LESS THAN 70 SQ FT & HALLWAYS
- ALL NEW RECESSED LIGHTING SHALL COMPLY WITH THE REFERENCE JOINT APPENDIX JAB AND SHALL NOT CONTAIN SCREW BASE SOCKET. CA ENERGY SECTIONS 150.0 (K) 1 C.
- RECESSED LIGHTING FIXTURES TO BE LISTED FOR ZERO CLEARANCE INSULATION CONTACT (IC) IN ACCORDANCE W/ CEC 150(K)(L)(A).
- ALL PROPOSED LIGHTING TO BE HIGH EFFICACY IN ACCORDANCE WITH CEC 150, 0 (K)(L)(A)
- ALL NEW OUTDOOR LIGHTING, IF ANY, IS TO BE HIGH-EFFICACY, TO BE CONTROLLED BY AN ON/OFF SWITCH AND INCLUDE ONE OF THE FOLLOWING PER CA ENERGY CODE SECTION 150.0 (K) 3A.:
 - PHOTOCELL AND MOTION SENSOR
 - PHOTOCONTROL AND AUTOMATIC TIME SWITCH CONTROL
 - ASTRONOMICAL TIME CLOCK CONTROL.
 - ENERGY MANAGEMENT CONTROL SYSTEM

Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

--	--

REMODEL & ADDITION	OWNER:
--------------------	--------

Drawing By:
Chris Klimen
klimen@att.net
PH: 510.928.1359
Peter Christopher Klimen
<small>DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN EMAIL:KLIMEN@ATT.NET DATE: 00/0000</small>

CODE & CONSTRUCTION NOTES

A0.2

INSPECTOR SIGNOFF

CHAPTER 3 GREEN BUILDING SECTION 301 GENERAL

301.1 SCOPE. Buildings shall be designed to include the green building measures specified as mandatory in the application checklists contained in this code. Voluntary green building measures are also included in the application checklists and may be included in the design and construction of structures covered by this code, but are not required unless adopted by a city, county, or city and county as specified in Section 101.7.

301.1.1 Additions and alterations. [HCD] The mandatory provisions of Chapter 4 shall be applied to additions or alterations of existing residential buildings where the addition or alteration increases the building's conditioned area, volume, or size. The requirements shall apply only to and/or within the specific area of the addition or alteration.

Note: On and after January 1, 2014, residential buildings undergoing permitted alterations, additions, or improvements shall replace noncompliant plumbing fixtures with water-conserving plumbing fixtures. Plumbing fixture replacement is required prior to issuance of a certificate of final completion, certificate of occupancy or final permit approval by the local building department. See Civil Code Section 1101.1, et seq., for the definition of a noncompliant plumbing fixture, types of residential buildings affected and other important enactment dates.

301.2 LOW-RISE AND HIGH-RISE RESIDENTIAL BUILDINGS. [HCD] The provisions of individual sections of CALGreen may apply to either low-rise residential buildings high-rise residential buildings, or both. Individual sections will be designated by banners to indicate where the section applies specifically to low-rise only (LR) or high-rise only (HR). When the section applies to both low-rise and high-rise buildings, no banner will be used.

SECTION 302 MIXED OCCUPANCY BUILDINGS

302.1 MIXED OCCUPANCY BUILDINGS. In mixed occupancy buildings, each portion of a building shall comply with the specific green building measures applicable to each specific occupancy.

ABBREVIATION DEFINITIONS:

HCD	Department of Housing and Community Development
BSC	California Building Standards Commission
DSDA-SS	Division of the State Architect, Structural Safety
OSHPD	Office of Statewide Health Planning and Development
LR	Low Rise
HR	High Rise
AA	Additions and Alterations
N	New

CHAPTER 4 RESIDENTIAL MANDATORY MEASURES

DIVISION 4.1 PLANNING AND DESIGN

SECTION 4.102 DEFINITIONS

4.102.1 DEFINITIONS

The following terms are defined in Chapter 2 (and are included here for reference)

FRENCH DRAIN. A trench, hole or other depressed area loosely filled with rock, gravel, fragments of brick or similar pervious material used to collect or channel drainage or runoff water.

WATTLES. Wattles are used to reduce sediment in runoff. Wattles are often constructed of natural plant materials such as hay, straw or similar material shaped in the form of tubes and placed on a downflow slope. Wattles are also used for perimeter and inlet controls.

4.106 SITE DEVELOPMENT

4.106.1 GENERAL. Preservation and use of available natural resources shall be accomplished through evaluation and careful planning to minimize negative effects on the site and adjacent areas. Preservation of slopes, management of storm water drainage and erosion controls shall comply with this section.

4.106.2 STORM WATER DRAINAGE AND RETENTION DURING CONSTRUCTION. Projects which disturb less than one acre of soil and are not part of a larger common plan of development which in total disturbs one acre or more, shall manage storm water drainage during construction. In order to manage storm water drainage during construction, one or more of the following measures shall be implemented to prevent flooding of adjacent property, prevent erosion and retain soil runoff on the site.

- Retention basins of sufficient size shall be utilized to retain storm water on the site.
- Where there is evidence substantiating that meeting the requirements will alter the local utility infrastructure design requirements on the utility side of the meter so as to increase the utility side cost to the homeowner or developer by more than \$400.00 per unit.
- Compliance with a lawfully enacted storm water management ordinance.

4.106.3 GRADING AND PAVING. Construction plans shall indicate how the site grading or drainage system will manage all surface water flows to keep water from entering buildings. Examples of methods to manage surface water include, but are not limited to, the following:

- Swales
- Water collection and disposal systems
- French drains
- Water retention gardens
- Other water measures which keep surface water away from buildings and aid in groundwater recharge.

Exception: Additions and alterations not altering the drainage path.

4.106.4 Electric vehicle (EV) charging for new construction. New construction shall comply with Sections 4.106.4.1 and 4.106.4.2 to facilitate future installation and use of EV chargers. Electric vehicle supply equipment (EVSE) shall be installed in accordance with the *California Electrical Code*, Article 625.

Exceptions: On a case-by-case basis, where the local enforcing agency has determined EV charging and infrastructure are not feasible based upon one or more of the following conditions:

- Where there is no commercial power supply.
- Where there is evidence substantiating that meeting the requirements will alter the local utility infrastructure design requirements on the utility side of the meter so as to increase the utility side cost to the homeowner or developer by more than \$400.00 per unit.

4.106.4.1 New one- and two-family dwellings and townhouses with attached private garages. For each dwelling unit, install a listed raceway to accommodate a dedicated 208/240-volt branch circuit. The raceway shall not be less than trade size 1 (nominal 1-inch inside diameter). The raceway shall originate at the main service or subpanel and shall terminate into a listed cabinet, box or other enclosure in close proximity to the proposed location of an EV charger. Raceways are required to be continuous at enclosed, inaccessible or concealed areas and spaces. The service panel and/or subpanel shall provide capacity to install a 40-ampere minimum dedicated branch circuit and space(s) reserved to permit installation of a branch circuit overcurrent protective device.

4.106.4.1.1 Identification. The service panel or subpanel circuit directory shall identify the overcurrent protective device space(s) reserved for future EV charging as "EV CAPABLE". The raceway termination location shall be permanently and visibly marked as "EV CAPABLE".

4.106.4.2 New multifamily dwellings. Where 17 or more multifamily dwelling units are constructed on a building site, 3 percent of the total number of parking spaces provided for all types of parking facilities, but in no case less than one, shall be electric vehicle charging stations (EV spaces) capable of supporting future EVSE. Calculations for the number of EV spaces shall be rounded up to the nearest whole number.

Note: Construction documents are intended to demonstrate the project's capability and capacity for facilitating future EV charging. There is no requirement for EV spaces to be constructed or available until EV chargers are installed for use.

4.106.4.2.1 Electric vehicle charging space (EV space) locations. Construction documents shall indicate the location of proposed EV spaces. At least one EV space shall be located in common use areas and available for use by all residents.

When EV chargers are installed, EV spaces required by Section 4.106.2.2, Item 3, shall comply with at least one of the following options:

- The EV space shall be located adjacent to an accessible parking space meeting the requirements of the *California Building Code*, Chapter 11A, to allow use of the EV charger from the accessible parking space.
- The EV space shall be located on an accessible route, as defined in the *California Building Code*, Chapter 2, to the building.

INSPECTOR SIGNOFF

CHAPTER 3 GREEN BUILDING SECTION 301 GENERAL

4.106.4.2.2 Electric vehicle charging space (EV space) dimensions. The EV space shall be designed to comply with the following:

- The minimum length of each EV space shall be 18 feet (5486 mm).
- The minimum width of each EV space shall be 9 feet (2743 mm).
- One in every 25 EV spaces, but not less than one EV space, shall have an 8-foot (2438 mm) wide minimum aisle. A 5-foot (1524 mm) wide minimum aisle shall be permitted provided the minimum width of the EV space is 12 feet (3658 mm).

a. Surface slope for this EV space and the aisle shall not exceed 1 unit vertical in 48 units horizontal (2.083 percent slope) in any direction.

4.106.4.2.3 Single EV space required. Install a listed raceway capable of accommodating a 208/240-volt dedicated branch circuit. The raceway shall not be less than trade size 1 (nominal 1-inch inside diameter). The raceway shall originate at the main service or subpanel and shall terminate into a listed cabinet, box or enclosure in close proximity to the proposed location of the EV spaces. Construction documents shall identify the raceway termination point. The service panel and/or subpanel shall provide capacity to install a 40-ampere minimum dedicated branch circuit and space(s) reserved to permit installation of a branch circuit overcurrent protective device.

4.106.4.2.4 Multiple EV spaces required. Construction documents shall indicate the raceway termination point and proposed location of future EV spaces and EV chargers. Construction documents shall also provide information on amperage of future EVSE, raceway method(s), wiring schematics and electrical load calculations to verify that the electrical panel service capacity and electrical system, including any on-site distribution transformer(s), have sufficient capacity to simultaneously charge all EVs all required EV spaces at the full rated amperage of the EVSE. Plan design shall be based upon a 40-ampere minimum branch circuit. Raceways and related components that are planned to be installed underground, enclosed, inaccessible or in concealed areas and spaces shall be installed at the time of original construction.

4.106.4.2.5 Identification. The service panel or subpanel circuit directory shall identify the overcurrent protective device space(s) reserved for future EV charging purposes as "EV CAPABLE" in accordance with the *California Electrical Code*.

Notes:

- The California Department of Transportation adopts and publishes the "California Manual on Uniform Traffic Control Devices (California MUTCD)" to provide uniform standards and specifications for all official traffic control devices in California. Zero Emission Vehicle Signs and Pavement Markings can be found in the New Policies & Directives Number 13-01. Website: www.dot.ca.gov/trafficops/policy/13-01.pdf

- See Vehicle Code Section 22511 for EV charging space signage in off-street parking facilities and for use of EV charging spaces.

- The Governor's Office of Planning and Research (OPR) published a "Zero-Emission Vehicle Community Readiness Guidebook" which provides helpful information for local governments, residents and businesses. Website: http://opr.ca.gov/docs/ZEV_Guidebook.pdf.

DIVISION 4.2 ENERGY EFFICIENCY

4.201 GENERAL

4.201.1 SCOPE. For the purposes of mandatory energy efficiency standards in this code, the California Energy Commission will continue to adopt mandatory standards.

DIVISION 4.3 WATER EFFICIENCY AND CONSERVATION

4.303 INDOOR WATER USE

4.303.1 WATER CONSERVING PLUMBING FIXTURES AND FITTINGS. Plumbing fixtures (water closets and urinals) and fittings (faucets and showerheads) shall comply with the following:

4.303.1.1 Water Closets. The effective flush volume of all water closets shall not exceed 1.28 gallons per flush. Tank-type water closets shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Tank-type Toilets.

Note: The effective flush volume of dual flush toilets is defined as the composite, average flush volume of two reduced flushes and one full flush.

4.303.1.2 Urinals. The effective flush volume of wall mounted urinals shall not exceed 0.125 gallons per flush. The effective flush volume of all other urinals shall not exceed 0.5 gallons per flush.

4.303.1.3 Showerheads.

4.303.1.3.1 Single Showerhead. Showerheads shall have a maximum flow rate of not more than 2.0 gallons per minute at 80 psi. Showerheads shall be certified to the performance criteria of the U.S. EPA WaterSense Specification for Showerheads.

4.303.1.3.2 Multiple showerheads serving one shower. When a shower is served by more than one showerhead, the combined flow rate of all the showerheads and/or other shower outlets controlled by a single valve shall not exceed 2.0 gallons per minute at 80 psi, or the shower shall be designed to only allow one shower outlet to be in operation at a time.

Note: A hand-held shower shall be considered a showerhead.

4.303.1.4 Faucets.

4.303.1.4.1 Residential Lavatory Faucets. The maximum flow rate of residential lavatory faucets shall not exceed 1.2 gallons per minute at 60 psi. The minimum flow rate of residential lavatory faucets shall not be less than 0.8 gallons per minute at 20 psi.

4.303.1.4.2 Lavatory Faucets in Common and Public Use Areas. The maximum flow rate of lavatory faucets installed in common and public use areas (outside of dwellings or sleeping units) in residential buildings shall not exceed 0.5 gallons per minute at 60 psi.

4.303.1.4.3 Metering Faucets. Metering faucets when installed in residential buildings shall not deliver more than 0.25 gallons per cycle.

4.303.1.4.4 Kitchen Faucets. The maximum flow rate of kitchen faucets shall not exceed 1.8 gallons per minute at 60 psi. Kitchen faucets may temporarily increase the flow above the maximum rate, but not to exceed 2.2 gallons per minute at 60 psi, and must default to a maximum flow rate of 1.8 gallons per minute at 60 psi.

Note: Where complying faucets are unavailable, aerators or other means may be used to achieve reduction.

4.303.2 STANDARDS FOR PLUMBING FIXTURES AND FITTINGS. Plumbing fixtures and fittings shall be installed in accordance with the *California Plumbing Code*, and shall meet the applicable standards referenced in Table 1701.1 of the *California Plumbing Code*.

NOTE: THIS TABLE COMPILES THE DATA IN SECTION 4.303.1, AND IS INCLUDED AS A CONVENIENCE FOR THE USER.

FIXTURE TYPE	FLOW RATE
SHOWER HEADS (RESIDENTIAL)	2.0 GMP @ 80 PSI
LAVATORY FAUCETS (RESIDENTIAL)	MAX. 1.2 GPM @ 60 PSI MIN. 0.8 GPM @ 20 PSI
LAVATORY FAUCETS IN COMMON & PUBLIC USE AREAS	0.5 GPM @ 60 PSI
KITCHEN FAUCETS	1.8 GPM @ 60 PSI
METERING FAUCETS	0.25 GAL/CYCLE
WATER CLOSET	1.28 GAL/FLUSH
URINALS	0.125 GAL/FLUSH

INSPECTOR SIGNOFF

4.304 OUTDOOR WATER USE

4.304.1 IRRIGATION CONTROLLERS. Automatic irrigation system controllers for landscaping provided by the builder and installed at the time of final inspection shall comply with the following:

1. Controllers shall be weather- or soil moisture-based controllers that automatically adjust irrigation in response to changes in plants' needs as weather conditions change.

2. Weather-based controllers without integral rain sensors or communication systems that account for local rainfall shall have a separate wired or wireless rain sensor which connects or communicates with the controller(s). Soil moisture-based controllers are not required to have rain sensor input.

Note: More information regarding irrigation controller function and specifications is available from the Irrigation Association.

DIVISION 4.4 MATERIAL CONSERVATION AND RESOURCE EFFICIENCY

4.406 ENHANCED DURABILITY AND REDUCED MAINTENANCE

4.406.1 RODENT PROOFING. Annual spaces around pipes, electric cables, conduits or other openings in sole/bottom plates at exterior walls shall be protected against the passage of rodents by closing such openings with cement mortar, concrete masonry or a similar method acceptable to the enforcing agency.

4.408 CONSTRUCTION WASTE REDUCTION, DISPOSAL AND RECYCLING

4.408.1 CONSTRUCTION WASTE MANAGEMENT. Recycle and/or salvage for reuse a minimum of 65 percent of the non-hazardous construction and demolition waste in accordance with either Section 4.408.2, 4.408.3 or 4.408.4, or meet a more stringent local construction and demolition waste management ordinance.

Exceptions:

- Excavated soil and land-clearing debris.
- Alternate waste reduction methods developed by working with local agencies if diversion or recycle facilities capable of compliance with this item do not exist or are not located reasonably close to the jobsite.
- The enforcing agency may make exceptions to the requirements of this section when isolated jobsite are located in areas beyond the haul boundaries of the diversion facility.

4.408.2 CONSTRUCTION WASTE MANAGEMENT PLAN. Submit a construction waste management plan in conformance with Items 1 through 5. The construction waste management plan shall be updated as necessary and shall be available during construction for examination by the enforcing agency.

- Identify the construction and demolition waste materials to be diverted from disposal by recycling, reuse on the project or salvage for future use or sale.
- Specify if construction and demolition waste materials will be sorted on-site (source separated) or bulk mixed (single stream).
- Identify diversion facilities where the construction and demolition waste material collected will be taken.
- Identify construction methods employed to reduce the amount of construction and demolition waste generated.
- Specify that the amount of construction and demolition waste materials diverted shall be calculated by weight or volume, but not by both.

4.408.3 WASTE MANAGEMENT COMPANY. Utilize a waste management company, approved by the enforcing agency, which can provide verifiable documentation that the percentage of construction and demolition waste material diverted from the landfill complies with Section 4.408.1.

Note: The owner or contractor may make the determination if the construction and demolition waste materials will be diverted by a waste management company.

4.408.4 WASTE STREAM REDUCTION ALTERNATIVE [LR]. Projects that generate a total combined weight of construction and demolition waste disposed of in landfills, which do not exceed 3.4 lbs./sq.ft. of the building area shall meet the minimum 65% construction waste reduction requirement in Section 4.408.1.

4.408.4.1 WASTE STREAM REDUCTION ALTERNATIVE. Projects that generate a total combined weight of construction and demolition waste disposed of in landfills, which do not exceed 2 lbs./sq.ft. of the building area, shall meet the minimum 65% construction waste reduction requirement in Section 4.408.1.

4.408.5 DOCUMENTATION. Documentation shall be provided to the enforcing agency which demonstrates compliance with Section 4.408.2, Items 1 through 5, Section 4.408.3 or Section 4.408.4.

Notes:

- Sample forms found in "A Guide to the California Green Building Standards Code (Residential)" located at www.hcd.ca.gov/CALGreen.html may be used to assist in documenting compliance with this section.
- Mixed construction and demolition debris (C & D) processors can be located at the California Department of Resources Recycling and Recovery (CalRecycle).

4.410 BUILDING MAINTENANCE AND OPERATION

4.410.1 OPERATION AND MAINTENANCE MANUAL. At the time of final inspection, a manual, compact disc, web-based reference or other media acceptable to the enforcing agency which includes all of the following shall be placed in the building:

- Directions to the owner or occupant that the manual shall remain with the building throughout the life cycle of the structure.
- Operation and maintenance instructions for the following:
 - Equipment and appliances, including water-saving devices and systems, HVAC systems, photovoltaic systems, electric vehicle chargers, water-heating systems and other major appliances and equipment.
 - Roof and yard drainage, including gutters and downspouts.
 - Space conditioning systems, including condensers and air filters.
 - Landscape irrigation systems.
 - Water reuse systems.
- Information from local utility, water and waste recovery providers on methods to further reduce resource consumption, including recycle programs and locations.
- Public transportation and/or carpool options available in the area.
- Educational material on the positive impacts of an interior relative humidity between 30-60 percent and what methods an occupant may use to maintain the relative humidity level in that range.
- Information about water-conserving landscape and irrigation design and controllers which conserve water.
- Instructions for maintaining gutters and downspouts and the importance of diverting water at least 5 feet away from the foundation.
- Information on required routine maintenance measures, including, but not limited to, caulking, painting, grading around the building, etc.
- Information about state solar energy and incentive programs available.
- A copy of all special inspectors verifications required by the enforcing agency or this [California Green Building Standards] code.

4.410.2 RECYCLING BY OCCUPANTS. Where 5 or more multifamily dwelling units are constructed on a building site, provide readily accessible area(s) that serves all buildings on the site and is identified for the depositing, storage and collection of non-hazardous materials for recycling, including (at a minimum) paper, corrugated cardboard, glass, plastics, organic waste, and metals, or meet a lawfully enacted local recycling ordinance, if more restrictive.

DIVISION 4.5 ENVIRONMENTAL QUALITY

SECTION 4.501 GENERAL

4.501.1 Scope. The provisions of this chapter shall outline means of reducing the quality of air contaminants that are odorous, irritating and/or harmful to the comfort and well being of a building's installers, occupants and neighbors.

SECTION 4.502 DEFINITIONS

5.102.1 DEFINITIONS

The following terms are defined in Chapter 2 (and are included here for reference)

AGRIFIBER PRODUCTS. Agrifiber products include wheatboard, strawboard, panel substrates and door cores, not including furniture, fixtures and equipment (FF&E) not considered base building elements.

COMPOSITE WOOD PRODUCTS. Composite wood products include hardwood plywood, particleboard and medium density fiberboard. "Composite wood products" does not include hardboard, structural plywood, structural panels, structural composite lumber, oriented strand board, glued laminated timber, prefabricated wood I-joists or finger-jointed lumber, all as specified in California Code of regulations (CCR), title 17, Section 93120.1.

DIRECT-VENT APPLIANCE. A fuel-burning appliance with a sealed combustion system that draws all air for combustion from the outside atmosphere and discharges all flue gases to the outside atmosphere.

INSPECTOR SIGNOFF

MAXIMUM INCREMENTAL REACTIVITY (MIR). The maximum change in weight of ozone formed by adding a compound to the "Base Reactive Organic Gas (ROG) Mixture" per weight of compound added, expressed to hundredths of a gram (g O₃/g ROG).

Note: MIR values for individual compounds and hydrocarbon solvents are specified in CCR, Title 17, Sections 94700 and 94701.

MOISTURE CONTENT. The weight of the water in wood expressed in percentage of the weight of the oven-dry wood.

PRODUCT-WEIGHTED MIR (PWMIR). The sum of all weighted-MIR for all ingredients in a product subject to this article. The PWMIR is the total product reactivity expressed to hundredths of a gram of ozone formed per gram of product (excluding container and packaging).

Note: PWMIR is calculated according to equations found in CCR, Title 17, Section 94521 (a).

REACTIVE ORGANIC COMPOUND (ROC). Any compound that has the potential, once emitted, to contribute to ozone formation in the troposphere.

VOC. A volatile organic compound (VOC) broadly defined as a chemical compound based on carbon chains or rings with vapor pressures greater than 0.1 millimeters of mercury at room temperature. These compounds typically contain hydrogen and may contain oxygen, nitrogen and other elements. See CCR Title 17, Section 94508(a).

4.503 FIREPLACES

4.503.1 GENERAL. Any installed gas fireplace shall be a direct-vent sealed-combustion type. Any installed woodstove or pellet stove shall comply with U.S. EPA New Source Performance Standards (NSPS) emission limits as applicable, and shall have a permanent label indication they are certified to meet the emission limits. Woodstoves, pellet stoves and fireplaces shall also comply with applicable local ordinances.

4.504 POLLUTANT CONTROL

4.504.1 COVERING OF DUCT OPENINGS & PROTECTION OF MECHANICAL EQUIPMENT DURING CONSTRUCTION. At the time of rough installation, during storage on the construction site and until final start-up of the heating, cooling and ventilating equipment, all duct and other related air distribution component openings shall be covered with tape, plastic, sheet metal or other methods acceptable to the enforcing agency to reduce the amount of water, dust or debris which may enter the system.

4.504.2 FINISH MATERIAL POLLUTANT CONTROL. Finish materials shall comply with this section.

4.504.2.1 Adhesives, Sealants and Caulks. Adhesives, sealant and caulks used on the project shall meet the requirements of the following standards unless more stringent local or regional air pollution or air quality management district rules apply:

1. Adhesives, adhesive bonding primers, adhesive primers, sealants, sealant primers and caulks shall comply with local or regional air pollution control or air quality management district rules where applicable or SCAQMD Rule 1168 VOC limits, as shown in Table 4.504.1 or 4.504.2, as applicable. Such products also shall comply with the Rule 1168 prohibition on the use of certain toxic compounds (chloroform, ethylene dichloride, methylene chloride, perchloroethylene and trichloroethylene), except for aerosol products, as specified in Subsection 2 below.

2. Aerosol adhesives, and smaller unit sizes of adhesives, and sealant or caulking compounds (in units of product, less packaging, which do not weigh more than 1 pound and do not consist of more than 16 fluid ounces) shall comply with statewide VOC standards and other requirements, including prohibitions on use of certain toxic compounds, of *California Code of Regulations*, Title 17, commencing with section 94507.

4.504.2.2 Paints and Coatings. Architectural paints and coatings shall comply with VOC limits in Table 1 of the ARB Architectural Suggested Control Measure, as shown in Table 4.504.3, unless more stringent local limits apply. The VOC content limit for coatings that do not meet the definitions for the specialty coatings categories listed in Table 4.504.3 shall be determined by classifying the coating as a Flat, Nonflat or Nonflat-High Gloss coating, based on its gloss, as defined in subsections 4.21, 4.36, and 4.37 of the 2007 California Air Resources Board, Suggested Control Measure, and the corresponding Flat, Nonflat or Nonflat-High Gloss VOC limit in Table 4.504.3 shall apply.

4.504.2.3 Aerosol Paints and Coatings. Aerosol paints and coatings shall meet the Product-weighted MIR Limits for ROC in Section 94522(a)(2) and other requirements, including prohibitions on use of certain toxic compounds and ozone depleting substances, in Sections 94522(b)(1) and (f)(1) of *California Code of Regulations*, Title 17, commencing with Section 94520; and in areas under the jurisdiction of the Bay Area Air Quality Management District additionally comply with the percent VOC by weight of product limits of Regulation 8, Rule 49.

4.504.2.4 Verification. Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following:

- Manufacturer's product specification.
- Field verification of on-site product containers.

4.504.2.5 Verification. Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following:

- Manufacturer's product specification.
- Field verification of on-site product containers.

4.504.2.6 Verification. Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following:

- Manufacturer's product specification.
- Field verification of on-site product containers.

4.504.2.7 Verification. Verification of compliance with this section shall be provided at the request of the enforcing agency. Documentation may include, but is not limited to, the following:

- Manufacturer's product specification.
- Field verification of on-site product containers.

TABLE 4.504.1 - ADHESIVE VOC LIMIT_{1,2}

(Less Water and Less Exempt Compounds in Grams per Liter)

ARCHITECTURAL APPLICATIONS	CURRENT VOC LIMIT
INDOOR CARPET ADHESIVES	50
CARPET PAD ADHESIVES	50
OUTDOOR CARPET ADHESIVES	150
WOOD FLOORING ADHESIVES	100
RUBBER FLOOR ADHESIVES	60
SUBFLOOR ADHESIVES	60
CERAMIC TILE ADHESIVES	50
VCT & ASPHALT TILE ADHESIVES	50
DRYWALL & PANEL ADHESIVES	50
COVE BASE ADHESIVES	50
MULTIPURPOSE CONSTRUCTION ADHESIVE	70
STRUCTURAL GLAZING ADHESIVES	100
SINGLE-PLY ROOF MEMBRANE ADHESIVES	250
OTHER ADHESIVES NOT LISTED	50
SPECIALTY APPLICATIONS	
PVC WELDING	510
CPVC WELDING	490
ABS WELDING	325
PLASTIC CEMENT WELDING	250
ADHESIVE PRIMER FOR PLASTIC	550
CONTACT ADHESIVE	80
SPECIAL PURPOSE CONTACT ADHESIVE	250
STRUCTURAL WOOD MEMBER ADHESIVE	140
TOP & TRIM ADHESIVE	250
SUBSTRATE SPECIFIC APPLICATIONS	
METAL TO METAL	30
PLASTIC FOAMS	50
POROUS MATERIAL (EXCEPT WOOD)	50
WOOD	30
FIBERGLASS	80

1. IF AN ADHESIVE IS USED TO BOND DISSIMILAR SUBSTRATES TOGETHER, THE ADHESIVE WITH THE HIGHEST VOC CONTENT SHALL BE ALLOWED.

INSPECTOR SIGNOFF

TABLE 4.504.2 - SEALANT VOC LIMIT

Table with 2 columns: SEALANTS, CURRENT VOC LIMIT. Rows include ARCHITECTURAL, MARINE DECK, NONMEMBRANE ROOF, ROADWAY, SINGLE-PLY ROOF MEMBRANE, OTHER, SEALANT PRIMERS, ARCHITECTURAL, NON-POROUS, POROUS, MODIFIED BITUMINOUS, MARINE DECK, OTHER.

TABLE 4.504.3 - VOC CONTENT LIMITS FOR ARCHITECTURAL COATINGS

Table with 2 columns: COATING CATEGORY, CURRENT VOC LIMIT. Rows include FLAT COATINGS, NON-FLAT COATINGS, NONFLAT-HIGH GLOSS COATINGS, SPECIALTY COATINGS, ALUMINUM ROOF COATINGS, BASEMENT SPECIALTY COATINGS, BITUMINOUS ROOF COATINGS, BITUMINOUS ROOF PRIMERS, BOND BREAKERS, CONCRETE CURING COMPOUNDS, CONCRETE/MASONRY SEALERS, DRIVEWAY SEALERS, DRY FOG COATINGS, FAUX FINISHING COATINGS, FIRE RESISTIVE COATINGS, FLOOR COATINGS, FORM-RELEASE COMPOUNDS, GRAPHIC ARTS COATINGS (SIGN PAINTS), HIGH TEMPERATURE COATINGS, INDUSTRIAL MAINTENANCE COATINGS, LOW SOLIDS COATINGS, MAGNESITE CEMENT COATINGS, MASTIC TEXTURE COATINGS, METALLIC PIGMENTED COATINGS, MULTICOLOR COATINGS, PRETREATMENT WASH PRIMERS, PRIMERS, SEALERS, & UNDERCOATERS, REACTIVE PENETRATING SEALERS, RECYCLED COATINGS, ROOF COATINGS, RUST PREVENTATIVE COATINGS, SHELLACS, CLEAR, OPAQUE, SPECIALTY PRIMERS, SEALERS & UNDERCOATERS, STAINS, STONE CONSOLIDANTS, SWIMMING POOL COATINGS, TRAFFIC MARKING COATINGS, TUB & TILE REFINISH COATINGS, WATERPROOFING MEMBRANES, WOOD COATINGS, WOOD PRESERVATIVES, ZINC-RICH PRIMERS.

1. GRAMS OF VOC PER LITER OF COATING, INCLUDING WATER & EXEMPT COMPOUNDS
2. THE SPECIFIED LIMITS REMAIN IN EFFECT UNLESS REVISED LIMITS ARE LISTED IN SUBSEQUENT COLUMNS IN THE TABLE.
3. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIFORNIA AIR RESOURCES BOARD, ARCHITECTURAL COATINGS SUGGESTED CONTROL MEASURE, FEB. 1, 2008. MORE INFORMATION IS AVAILABLE FROM THE AIR RESOURCES BOARD.

INSPECTOR SIGNOFF

TABLE 4.504.5 - FORMALDEHYDE LIMITS:

Table with 2 columns: PRODUCT, CURRENT LIMIT. Rows include HARDWOOD PLYWOOD VENEER CORE, HARDWOOD PLYWOOD COMPOSITE CORE, PARTICLE BOARD, MEDIUM DENSITY FIBERBOARD, THIN MEDIUM DENSITY FIBERBOARD.

1. VALUES IN THIS TABLE ARE DERIVED FROM THOSE SPECIFIED BY THE CALIF. AIR RESOURCES BOARD, AIR TOXICS CONTROL MEASURE FOR COMPOSITE WOOD AS TESTED IN ACCORDANCE WITH ASTM E 1333. FOR ADDITIONAL INFORMATION, SEE CALIF. CODE OF REGULATIONS, TITLE 17, SECTIONS 93120 THROUGH 93120.12.
2. THIN MEDIUM DENSITY FIBERBOARD HAS A MAXIMUM THICKNESS OF 5/16" (8 MM).

DIVISION 4.5 ENVIRONMENTAL QUALITY (continued)

4.504.3 CARPET SYSTEMS. All carpet installed in the building interior shall meet the testing and product requirements of at least one of the following:

- 1. Carpet and Rug Institute's Green Label Plus program.
2. California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers" Version 1.1, February 2010 (also known as Specification 01350).
3. NSF/ANSI 140 at the Gold level.
4. Scientific Certifications Systems Indoor Advantage™ Gold.

4.504.3.1 Carpet cushion. All carpet cushion installed in the building interior shall meet the requirements of the Carpet and Rug Institute's Green Label program.

4.504.3.2 Carpet adhesive. All carpet adhesive shall meet the requirements of Table 4.504.1.

4.504.4 RESILIENT FLOORING SYSTEMS. Where resilient flooring is installed, at least 80% of floor area receiving resilient flooring shall comply with one or more of the following:

- 1. Products compliant with the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers," in the Collaborative for High Performance Schools (CHPS) High Performance Products Database.
2. Products certified under UL GREENGUARD Gold (formerly the Greenguard Children & Schools program).
3. Certification under the Resilient Floor Covering Institute (RFCI) FloorScore program.
4. Meet the California Department of Public Health, "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers", Version 1.1, February 2010 (also known as Specification 01350).

4.504.5 COMPOSITE WOOD PRODUCTS. Hardwood plywood, particleboard and medium density fiberboard composite wood products used on the interior or exterior of the buildings shall meet the requirements for formaldehyde as specified in ARI's Air Toxics Control Measure for Composite Wood (17 CCR 93120 et seq.), by or before the dates specified in those sections, as shown in Table 4.504.5

4.504.5.1 Documentation. Verification of compliance with this section shall be provided as requested by the enforcing agency. Documentation shall include at least one of the following:

- 1. Product certifications and specifications.
2. Chain of custody certifications.
3. Product labeled and invoiced as meeting the Composite Wood Products regulation (see CCR, Title 17, Section 93120, et seq.).
4. Exterior grade products marked as meeting the PS-1 or PS-2 standards of the Engineered Wood Association, the Australian AS/NZS 2269, European 636 35 standards, and Canadian CSA 0121, CSA 0151, CSA 0153 and CSA 0325 standards.
5. Other methods acceptable to the enforcing agency.

4.505 INTERIOR MOISTURE CONTROL
4.505.1 General. Buildings shall meet or exceed the provisions of the California Building Standards Code.

4.505.2 CONCRETE SLAB FOUNDATIONS. Concrete slab foundations required to have a vapor retarder by California Building Code, Chapter 19, or concrete slab-on-ground floors required to have a vapor retarder by the California Residential Code, Chapter 5, shall also comply with this section.

4.505.2.1 Capillary break. A capillary break shall be installed in compliance with at least one of the following:

- 1. A 4-inch (101.6 mm) thick base of 1/2 inch (12.7mm) or larger clean aggregate shall be provided with a vapor barrier in direct contact with concrete and a concrete mix design, which will address bleeding, shrinkage, and curling, shall be used. For additional information, see American Concrete Institute, ACI 302.2R-06.
2. Other equivalent methods approved by the enforcing agency.
3. A slab design specified by a licensed design professional.

4.505.3 MOISTURE CONTENT OF BUILDING MATERIALS. Building materials with visible signs of water damage shall not be installed. Wall and floor framing shall not be enclosed when the framing members exceed 19 percent moisture content. Moisture content shall be verified in compliance with the following:

- 1. Moisture content shall be determined with either a probe-type or contact-type moisture meter. Equivalent moisture verification methods may be approved by the enforcing agency and shall satisfy requirements found in Section 101.8 of this code.
2. Moisture readings shall be taken at a point 2 feet (610 mm) to 4 feet (1219 mm) from the grade stamped end of each piece verified.
3. At least three random moisture readings shall be performed on wall and floor framing with documentation acceptable to the enforcing agency provided at the time of approval to enclose the wall and floor framing.

Insulation products which are visibly wet or have a high moisture content shall be replaced or allowed to dry prior to enclosure in wall or floor cavities. Wet-applied insulation products shall follow the manufacturers' drying recommendations prior to enclosure.

4.506 INDOOR AIR QUALITY AND EXHAUST
4.506.1 Bathroom exhaust fans. Each bathroom shall be mechanically ventilated and shall comply with the following:

- 1. Fans shall be ENERGY STAR compliant and be ducted to terminate outside the building.
2. Unless functioning as a component of a whole house ventilation system, fans must be controlled by a humidity control.
a. Humidity controls shall be capable of adjustment between a relative humidity range less than or equal to 50% to a maximum of 80%. A humidity control may utilize manual or automatic means of adjustment.
b. A humidity control may be a separate component to the exhaust fan and is not required to be integral (i.e., built-in)

Notes:

- 1. For the purposes of this section, a bathroom is a room which contains a bathtub, shower or tub/shower combination.
2. Lighting integral to bathroom exhaust fans shall comply with the California Energy Code.

4.507 ENVIRONMENTAL COMFORT
4.807.2 HEATING AND AIR-CONDITIONING SYSTEM DESIGN. Heating and air conditioning systems shall be sized, designed and have their equipment selected using the following methods:

- 1. The heat loss and heat gain is established according to ANSI/ACCA 2 Manual J - 2011 (Residential Load Calculation), ASHRAE handbooks or other equivalent design software or methods.
2. Duct systems are sized according to ANSI/ACCA 1 Manual D - 2014 (Residential Duct Systems), ASHRAE handbooks or other equivalent design software or methods.
3. Select heating and cooling equipment according to ANSI/ACCA 3 Manual S - 2014 (Residential Equipment Selection), or other equivalent design software or methods.

Exception: Use of alternate design temperatures necessary to ensure the system functions are acceptable.

INSPECTOR SIGNOFF

CHAPTER 7 INSTALLER & SPECIAL INSPECTOR QUALIFICATIONS
702 QUALIFICATIONS
702.1 INSTALLER TRAINING. HVAC system installers shall be trained and certified in the proper installation of HVAC systems including ducts and equipment by a nationally or regionally recognized training or certification program.

Unlicensed persons may perform HVAC installations when under the direct supervision and responsibility of a person trained and certified to install HVAC systems or contractor licensed to install HVAC systems. Examples of acceptable HVAC training and certification programs include but are not limited to the following:

- 1. State certified apprenticeship programs.
2. Public utility training programs.
3. Training programs sponsored by trade, labor or statewide energy consulting or verification organizations.
4. Programs sponsored by manufacturing organizations.
5. Other programs acceptable to the enforcing agency.

702.2 SPECIAL INSPECTION [HCD]. When required by the enforcing agency, the owner or the responsible entity acting as the owner's agent shall employ one or more special inspectors to provide inspection or other duties necessary to substantiate compliance with this code. Special inspectors shall demonstrate competence to the satisfaction of the enforcing agency for the particular type of inspection or task to be performed. In addition to other certifications or qualifications acceptable to the enforcing agency, the following certifications or education may be considered by the enforcing agency when evaluating the qualifications of a special inspector:

- 1. Certification by a national or regional green building program or standard publisher.
2. Certification by a statewide energy consulting or verification organization, such as HERS raters, building performance contractors, and home energy auditors.
3. Successful completion of a third party apprentice training program in the appropriate trade.
4. Other programs acceptable to the enforcing agency.

Notes:

- 1. Special inspectors shall be independent entities with no financial interest in the materials or the project they are inspecting for compliance with this code.
2. HERS raters are special inspectors certified by the California Energy Commission (CEC) to rate homes in California according to the Home Energy Rating System (HERS).

[BSC] When required by the enforcing agency, the owner or the responsible entity acting as the owner's agent shall employ one or more special inspectors to provide inspection or other duties necessary to substantiate compliance with this code. Special inspectors shall demonstrate competence to the satisfaction of the enforcing agency for the particular type of inspection or task to be performed. In addition, the special inspector shall have a certification from a recognized state, national or international association, as determined by the local agency. The area of certification shall be closely related to the primary job function, as determined by the local agency.

Note: Special inspectors shall be independent entities with no financial interest in the materials or the project they are inspecting for compliance with this code.

703 VERIFICATIONS
703.1 DOCUMENTATION. Documentation used to show compliance with this code shall include but is not limited to, construction documents, plans, specifications, builder or installer certification, inspection reports, or other methods acceptable to the enforcing agency which demonstrate substantial conformance. When specific documentation or special inspection is necessary to verify compliance, that method of compliance will be specified in the appropriate section or identified applicable checklist.

INSPECTOR SIGNOFF

INSPECTOR SIGNOFF

Revision History

Table with 2 columns: Revision, Description. Rows include AS-BUILT, PRELIMINARY DESIGN, DESIGN, PERMIT SET, PLAN REVIEW COMMENTS, PLAN REVIEW COMMENTS.

REMODEL & ADDITION

OWNER:

Drawing By:

Chris Klimen

klimen@att.net

PH: 510.928.1359

Peter Christopher Klimen


DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL:KLIMEN@ATT.NET DATE: 00/0000

CAL GREEN REQUIREMENTS PAGE 2

G1.1

DURANT AVE


CENTER LINE OF DURANT AVE



(E) SITE PLAN
SCALE: 3/32"=1'-0"

DURANT AVE

CENTER LINE OF DURANT AVE



(N) SITE PLAN
SCALE: 3/32"=1'-0"

Revision History

	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:

Drawing By:

Chris Klimen

klimen@att.net

PH: 510.928.1359

Peter Christopher Klimen


DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL: KLIMEN@ATT.NET DATE: 00/00/00

SITE PLANS

A1.0


SITE NOTES:

- ANY AREA WHERE SOIL IS DISTURBED MUST BE IMMEDIATELY SURROUNDED BY STRAW WATTLES IN SUCH A WAY THAT ANY DRAINAGE PASSING THROUGH THE AREA WILL BE FILTERED (SEE SITE PLAN FOR ROUGH OUTLINE OF LOCATIONS WHERE WATTLES WILL BE REQUIRED).
- ROOF RUNOFF/DOWNSPOUTS SHALL BE ROUTED AWAY FROM EXCAVATED AREAS TO CITY STORM DRAIN OR VEGETATED AREAS ON THE PROPERTY. WATER MAY NOT BE ROUTED IN SUCH A WAY THAT IT DRAINS TO NEIGHBORING PROPERTIES
- A NON-PERMEABLE BARRIER SHALL BE ATTACHED TO AND SLOPE AWAY FROM THE STRUCTURE IN SUCH A WAY THAT WATER WILL NOT RUN UNDER THE HOUSE OR INTO THE NEW FOUNDATION EXCAVATIONS
- SPOILS ARE TO BE IMMEDIATELY REMOVED FROM THE SITE OR COVERED. ANY COVERING IS TO BE NON-PERMEABLE AND FIRMLY ANCHORED IN PLACE
- CARPORT QUALIFIES AS "LEGAL NONCONFORMING" AS DESCRIBED ON THE ACCESSORY STRUCTURE INFO SHEET



SEE STRUCTURAL PLANS FOR FRAMING DETAILS

2 ENLARGED PLAN
A1.11 SCALE: 1/2"=1'-0"



- CONSTRUCTION NOTES:**
- ANNULAR SPACES AROUND PIPES, ELECTRIC CABLES, CONDUITS OR OTHER OPENINGS IN SOLE/BOTTOM PLATES AT EXTERIOR WALLS SHALL BE PROTECTED AGAINST THE PASSAGE OF RODENTS BY CLOSING SUCH OPENINGS WITH CEMENT MORTAR, CONCRETE MASONRY OR A SIMILAR METHOD ACCEPTABLE TO THE ENFORCING AGENCY.
 - CONTRACTORS SHALL PROVIDE OWNER WITH ALL END USER INFORMATION & MAINTENANCE MANUALS FOR INSTALLED ITEMS & ALL OTHER REQUIRED INFORMATION DESCRIBED IN SECTION 4.410 ON SHEET G1.0 PRIOR TO BUILDING FINAL
 - ALL FINISH MATERIALS SHALL BE COMPLIANT WITH VOC AND OTHER TOXIC COMPOUND LIMITS AS OUTLINED IN SECTION 4.504 ON SHEETS G1.0 & G1.1. INCLUDING (BUT NOT LIMITED TO) ADHESIVES, SEALANTS, CAULKS, PAINTS, STAINS, COATINGS, CARPET & CARPET SYSTEMS, RESILIENT FLOORING, PARTICLEBOARD, MEDIUM DENSITY FIBERBOARD, PLYWOOD. DOCUMENTATION IS REQUIRED AS SPECIFIED IN SECTION 4.504.2.4 ON SHEET G1.0
 - MOISTURE CONTENT OF BUILDING MATERIALS SHALL BE VERIFIED AND DOCUMENTATION PROVIDED TO THE ENFORCING AGENCY AS OUTLINED IN SECTION 4.505.3 ON SHEET G1.1. DO NOT CLOSE ANY CONSTRUCTION PRIOR TO VERIFICATION

CRAWL SPACE VENTILATION:

PER CRC SECTION R408.1 - THE MINIMUM NET AREA OF VENTILATION OPENINGS SHALL BE NOT LESS THAN 1 SQUARE FOOT FOR EACH 150 SQUARE FEET OF UNDER-FLOOR SPACE AREA, UNLESS THE GROUND SURFACE IS COVERED BY A CLASS 1 VAPOR RETARDER MATERIAL. WHERE A CLASS 1 VAPOR RETARDER MATERIAL IS USED, THE MINIMUM NET AREA OF VENTILATION OPENINGS SHALL BE NOT LESS THAN 1 SQUARE FOOT FOR EACH 1,500 SQUARE FEET OF UNDER-FLOOR SPACE AREA.

ONE VENTILATION OPENING SHALL BE WITHIN 3 FEET (915 MM) OF EACH CORNER OF THE BUILDING.

VENTILATION OPENINGS SHALL BE COVERED FOR THEIR HEIGHT AND WIDTH WITH ANY OF THE FOLLOWING MATERIALS PROVIDED THAT THE LEAST DIMENSION OF THE COVERING SHALL NOT EXCEED 1/4 INCH (6.4 MM):

- PERFORATED SHEET METAL PLATES NOT LESS THAN 0.070 INCH (1.8 MM) THICK.
- EXPANDED SHEET METAL PLATES NOT LESS THAN 0.047 INCH (1.2 MM) THICK.
- CAST-IRON GRILL OR GRATING.
- EXTRUDED LOAD-BEARING BRICK VENTS.
- HARDWARE CLOTH OF 0.035 INCH (0.89 MM) WIRE OR HEAVIER.
- CORROSION-RESISTANT WIRE MESH, WITH THE LEAST DIMENSION BEING 1/8 INCH THICK.

NEW CRAWL SPACE SQUARE FEET = 1397 S.F.
1397/150 = 9.31 SQ. FT. (1341 SQ. IN.) OF VENTILATION OPENING REQUIRED

- 16 IN. X 8 IN. GSM VENTS = 70.7 SQ. IN. EACH - 19 VENTS OF THIS SIZE REQUIRED
- 16 IN. X 6 IN. GSM VENTS = 48.9 SQ. IN. EACH - 28 VENTS OF THIS SIZE REQUIRED
- 16 IN. X 4 IN. GSM VENTS = 27.2 SQ. IN. EACH - 52 VENTS OF THIS SIZE REQUIRED

LEGEND:

	EXISTING TO REMAIN
	EXISTING TO BE REMOVED
	NEW 2X4 WALL @ 16" O.C.
	EXTERIOR WALLS R-13 MIN INSULATION

Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
1	PLAN REVIEW COMMENTS
2	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:


Drawing By:
Chris Klimen
klimen@att.net
PH: 510.928.1359

Peter Christopher Klimen
DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL:KLIMEN@ATT.NET DATE: 00/00/00


CONSTRUCTION PLAN

1 CONSTRUCTION PLAN
A1.11 SCALE: 1/4"=1'-0"

A1.11



(E) ROOF PLAN
SCALE: 1/4"=1'-0"



(N) ROOF PLAN
SCALE: 1/4"=1'-0"

- ROOF NOTES:**
- ROOFING SPECIFICATION: TPO EPDM -060 MIL ICC# ESR-1463
 - NEW DOWNSPOUT DRAINS TO A SPLASH BLOCK TO VEGETATED AREAS. SEE ELEVATIONS (A2.1) FOR DOWNSPOUT LOCATION
 - EXISTING ROOF IN UNVENTED

ATTIC FREE VENTILATION:
PER CRC SECTION R806.2 THE MINIMUM NET FREE VENTILATING AREA SHALL BE 1/150 OF THE AREA OF THE VENTED SPACE.

VENTILATION OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM. VENTILATION OPENINGS HAVING A LEAST DIMENSION LARGER THAN 1/4 INCH (6.4 MM) SHALL BE PROVIDED WITH CORROSION-RESISTANT WIRE CLOTH SCREENING, HARDWARE CLOTH OR SIMILAR MATERIAL WITH OPENINGS HAVING A LEAST DIMENSION OF 1/16 INCH (1.6 MM) MINIMUM AND 1/4 INCH (6.4 MM) MAXIMUM.

WHERE EAVE OR CORNICE VENTS ARE INSTALLED, INSULATION SHALL NOT BLOCK THE FREE FLOW OF AIR. NOT LESS THAN A 1-INCH SPACE SHALL BE PROVIDED BETWEEN THE INSULATION AND THE ROOF SHEATHING AND AT THE LOCATION OF THE VENT.

ATTIC SQUARE FEET =
SECTION A = 518 SQ FT
SECTION B = 611 SQ FT
SECTION C = 182 SQ FT

NET FREE VENTILATION AREA (N.F.V.A.) REQUIRED:
SECTION A: 518/150X144 = 497 SQ IN - 8 EVENLY SPACED VENTS @ 16"W X 8"T REQUIRED
SECTION B: 611/150X144 = 587 SQ IN - 9 EVENLY SPACED VENTS @ 16"W X 8"T REQUIRED
SECTION C: 182/150X144 = 175 SQ IN - 2 VENTS @ 20"W X 14"T REQUIRED. SEE A2.1 FOR APPROXIMATE INSTALLATION LOCATION OF VENTING @ THE ADDITION



Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
△1	PLAN REVIEW COMMENTS
△2	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:


Drawing By:
Chris Klimen
klimen@att.net
PH: 510.928.1359

Peter Christopher Klimen
DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL: KLIMEN@ATT.NET DATE: 00/00/00

ROOF PLAN



A1.3

2016 CALIFORNIA BUILDING CODE					
TABLE 2304.10.1 FASTENING SCHEDULE					
CONNECTION	FASTENING _{a,m}	LOCATION	CONNECTION	FASTENING _{a,m}	LOCATION
1. JOIST TO SILL OR ORDER	3-8d COMMON (25°x0.131") 2-5d COMMON (12°x0.131") 3-3" 14 GAGE STAPLES	TOENAIL	20. 1" DIAGONAL BRACE TO EACH STUD AND PLATE	2-8d COMMON (25°x0.131") 2-5d COMMON (12°x0.131") 3-3" 14 GAGE STAPLES	FACE NAIL
2. BRIDGING TO JOIST	2-8d COMMON (25°x0.131") 2-5d COMMON (12°x0.131") 2-3" 14 GAGE STAPLES	TOENAIL EACH END	21. 1" SHEATHING TO EACH BEARING	3-8d COMMON (25°x0.131")	FACE NAIL
3. 1" SUBFLOOR OR LESS TO EACH JOIST	3-8d COMMON (25°x0.131")	FACE NAIL	22. WIDER THAN 1" SHEATHING TO EACH BEARING	3-8d COMMON (25°x0.131")	FACE NAIL
4. WIDER THAN 1" SUBFLOOR TO EACH JOIST	3-8d COMMON (25°x0.131")	FACE NAIL	23. BUILT-UP CORNER STUDS	16d COMMON (30°x0.162") 3" 14 GAGE STAPLES	24° O.C. 18° O.C. 18° O.C.
5. 2" SUBFLOOR TO JOIST OR ORDER	2-16d COMMON (35°x0.162")	BLIND AND FACE NAIL	24. BUILT-UP ORDER AND BEAMS	20d COMMON (4°x0.162") 32° O.C. 3" 14 GAGE STAPLES	FACE NAIL AT 16d STAGGERED ON OPPOSITE SIDES
6. SOLE PLATE TO JOIST OR BLOORING	16d (35°x0.162") AT 18" O.C. 3" 14 GAGE STAPLES AT 8" O.C. 3" 14 GAGE STAPLES AT 12" O.C.	TYPICAL FACE NAIL	25. 2" PLANKS	16d COMMON (35°x0.162")	FACE NAIL AT ENDS AND AT EACH SPLICE
SOLE PLATE TO JOIST OR BLOORING AT BRACED WALL PANEL	3"-16d (35°x0.162") AT 18" O.C. 4"-5d COMMON (12°x0.131") NAILS AT 18" O.C. 4"-3" 14 GAGE STAPLES AT 18" O.C.	BRACED WALL PANELS	26. COLLAR TIE TO RAFTER	3-16d COMMON (35°x0.162") 4"-3" 14 GAGE STAPLES	AT EACH BEARING
7. TOP PLATE TO STUD	2-16d COMMON (35°x0.162") 3"-5d COMMON (12°x0.131") NAILS 3"-3" 14 GAGE STAPLES	END NAIL	27. JACK RAFTER TO HP	3-16d COMMON (35°x0.162") 4"-3" 14 GAGE STAPLES	FACE NAIL
8. STUD TO SOLE PLATE	4-8d COMMON (25°x0.131") 4"-5d COMMON (12°x0.131") NAILS 3"-3" 14 GAGE STAPLES	TOENAIL	28. ROOF RAFTER TO 2-BY RIDGE BEAM	3-16d COMMON (35°x0.162") 4"-3" 14 GAGE STAPLES	TOENAIL
9. DOUBLE STUDS	16d (35°x0.162") AT 18" O.C. 3" 14 GAGE STAPLE AT 8" O.C. 3" 14 GAGE STAPLE AT 12" O.C.	FACE NAIL	29. JOIST TO BAND JOIST	3-16d COMMON (35°x0.162") 4"-3" 14 GAGE STAPLES	FACE NAIL
10. DOUBLE TOP PLATES	16d (35°x0.162") AT 18" O.C. 3" 14 GAGE STAPLE AT 12" O.C. 3" 14 GAGE STAPLE AT 12" O.C.	TYPICAL FACE NAIL	30. LEDGER STRIP	3-16d COMMON (35°x0.162") 4"-3" 14 GAGE STAPLES	FACE NAIL
DOUBLE TOP PLATES	8-16d COMMON (35°x0.162") 12"-5d COMMON (12°x0.131") NAILS 12"-3" 14 GAGE STAPLES	LAP SPLICE PER SIDE	31. WOOD STRUCTURAL PANELS AND PARTICLEBOARD, SUBFLOOR, ROOF AND WALL SHEATHING (TO FRAMING)	3/4" AND LESS 5/8" OR 5/4"	8d 12°x0.131" NAIL 18 GAGE
11. BLOORING BETWEEN JOISTS OR RAFTERS TO TOP PLATE	3-8d COMMON (25°x0.131") 3"-5d COMMON (12°x0.131") NAILS 3"-3" 14 GAGE STAPLES	TOENAIL	32. SINGLE FLOOR (COMBINATION SUBFLOOR-UNDERLAYMENT TO FRAMING)	3/4" AND LESS 3/8" TO 1" 1/4" TO 1/4"	8d 8d 10d or 8d
12. END JOIST TO TOP PLATE	8d (25°x0.131") AT 8" O.C. 3" 14 GAGE STAPLE AT 8" O.C. 3" 14 GAGE STAPLE AT 8" O.C.	TOENAIL	33. PANEL SIDING (TO FRAMING)	3/4" OR LESS 3/8"	8d 8d 8d
13. TOP PLATES, LAPS AND INTERSECTIONS	2-16d COMMON (35°x0.162") 3"-5d COMMON (12°x0.131") NAILS 3"-3" 14 GAGE STAPLES	FACE NAIL	34. FIBERBOARD SHEATHING	3/4"	NO.11 GAGE ROOFING NAIL 8d COMMON NAIL (25°x0.131") NO.16 GAGE STAPLE
14. CONTINUOUS HEADER, TWO PIECES	16d COMMON (35°x0.162")	18" O.C. ALONG EDGE	35. INTERIOR PANELING	3/4"	4d 8d
15. CEILING JOISTS TO PLATE	3-8d COMMON (25°x0.131") 2-5d COMMON (12°x0.131") 2-3" 14 GAGE STAPLES	TOENAIL			
16. CONTINUOUS HEADER TO STUD	4-8d COMMON (25°x0.131")	TOENAIL			
17. CEILING JOISTS, LAPS OVER PARTITIONS (SEE SECTION 2308.10.4.1, TABLE 2308.10.4.1)	3-16d COMMON (35°x0.162") MINIMUM 4"-5d COMMON (12°x0.131") NAILS 4"-3" 14 GAGE STAPLES	FACE NAIL			
18. CEILING JOISTS TO PARALLEL RAFTERS (SEE SECTION 2308.10.4.1, TABLE 2308.10.4.1)	3-16d COMMON (35°x0.162") MINIMUM 4"-5d COMMON (12°x0.131") NAILS 4"-3" 14 GAGE STAPLES	FACE NAIL			
19. RAFTERS TO PLATE (SEE SECTION 2308.10.1, TABLE 2308.10.1)	3-8d COMMON (25°x0.131") 2-5d COMMON (12°x0.131") 2-3" 14 GAGE STAPLES	TOENAIL			




1 SECTION VIEW
A5.1 SCALE: 1/2"=1'-0"

2 FRAMING DETAILS
A5.1 NOT TO SCALE



- VERIFY EXACT LOCATION OF STAIRS IN FIELD.
- STAIR RISER HEIGHT TO BE ESTABLISHED IN FIELD. RISER TO BE 4" MIN & 7 3/4" MAX
- HANDRAIL BETWEEN THE DIMENSIONS OF 34" & 38" REQUIRED ALONG ALL SLOPED SECTIONS OF STAIRS.
- THE OUTSIDE DIAMETER OF A CIRCULAR HANDRAIL MAY BE NO MORE THAN 1-1/4 INCHES AND NO GREATER THAN 2 INCHES. A NON-CIRCULAR MUST HAVE A PERIMETER DIMENSION OF AT LEAST 4 INCHES AND NO GREATER THAN 6-1/4 INCHES. THE MAXIMUM CROSS SECTION IS 2-1/4 INCHES.
- HANDRAIL SHALL NOT PROJECT MORE THAN 4 1/2 INCHES ON EITHER SIDE OF THE STAIRWAY; AND, THE CLEAR WIDTH OF THE STAIRWAY AT AND BELOW THE HANDRAIL HEIGHT, INCLUDING TREADS AND LANDINGS, SHALL BE NOT LESS THAN 31 1/2 INCHES WHERE A HANDRAIL IS INSTALLED ON ONE SIDE OF STAIRS PER R311.7.1 (27 INCHES MIN. WHERE HANDRAILS ARE PROVIDED ON BOTH SIDES.)
- HANDRAILS ATTACHED TO THE WALL MUST HAVE SPACE BETWEEN THE WALL AND THE RAIL OF AT LEAST 1-1/2 INCHES TO PROVIDE A GRASPABLE SURFACE.
- GUARDRAIL @ STAIRS MAY BE 34" TO 38" WHERE TOP SERVES AS HANDRAIL
- INSTALL BLOCKING AS NEEDED

3 STAIR DETAILS
A5.1 NOT TO SCALE



Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
1	PLAN REVIEW COMMENTS
2	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:

Drawing By:
Chris Klimen
klimen@att.net
PH: 510.928.1359

Peter Christopher Klimen
DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL:KLIMEN@ATT.NET DATE: 00/00/00

DETAILS

A5.1

WINDOW SCHEDULE											
MARK	ROOM	WIDTH	HEIGHT	HEAD HEIGHT	R.O. WIDTH	R.O. HEIGHT	JAMB	TYPE SEE KEY	HARDWARE SEE KEY	GLASS	NOTES
1	FAMILY ROOM	9'-3 1/2"	4'-4"					SL			RETROFIT WINDOW
2	FAMILY ROOM	2'-11"	2'-4"					SL			RETROFIT WINDOW
3	FAMILY ROOM	2'-11"	2'-4"					SL			RETROFIT WINDOW
4	KITCHEN	5'-0"	3'-0"					SL			RETROFIT WINDOW/NEW CONSTRUCTION - TBD
5	BEDROOM 2	5'-6"	3'-6"					SL			NEW WINDOW - LOWER SILL ELEVATION TO ACCOMMODATE NEW LARGER WINDOW HEIGHT. WINDOW TO HAVE 32" MIN CLEAR OPERABLE WIDTH
6	POWDER	3'-0"	3'-0"					SL	0		NEW WINDOW
7	BATH 2	3'-0"	3'-0"					SL		T & O	NEW WINDOW
8	BATH 2	3'-0"	1'-0"					SL		T & O	RETROFIT WINDOW
9	BEDROOM 3	6'-7"	3'-10"					SL			RETROFIT WINDOW
10	(E) BEDROOM 1	1'-2"	1'-2"					A			EXISTING TO REMAIN
11	BEDROOM 1	6'-7"	3'-10"					SL			RETROFIT WINDOW
12	BATH 1	2'-5"	2'-10"					SL		T & O	RETROFIT WINDOW
13	(E) DINING ROOM	1'-2"	1'-2"					A			EXISTING TO REMAIN
14	DINING ROOM	2'-11"	4'-4"					SL			RETROFIT WINDOW
15	DINING ROOM	5'-7"	4'-4"					SL			RETROFIT WINDOW
16	(E) BATH 1	1'-9"	11 1/2"					S			EXISTING TO REMAIN

KEY: VERIFY WINDOW SIZES BEFORE PLACING ORDER

C	CASEMENT	T	TEMPERED
DH	DOUBLE HUNG	S	SKYLIGHT
F	FIXED	E	EXISTING TO REMAIN
A	AWNING	O	OBSCURE
H	HOPPER		
SL	SLIDER		
SGD	SLIDING GLASS DOOR		


WINDOW NOTES:
U-FACTOR MUST BE 0.32 OR LOWER & SGHC
MUST BE 0.25 OR LOWER

DOOR SCHEDULE											
MARK	ROOM	WIDTH	HEIGHT	HEAD HEIGHT	R.O. WIDTH	R.O. HEIGHT	JAMB	TYPE SEE KEY	HARDWARE SEE KEY	GLASS	NOTES
A	FAMILY ROOM	3'-0"	6'-8"								EXTERIOR GRADE - ENTRY
B	BEDROOM 2	2'-6"	6'-8"								
C	BEDROOM 2	6'-0"	6'-8"					BP			
D	HALL	2'-8"	6'-8"					BF			2 DOORS - PROVIDE 100 SQ IN (MIN) MAKE-UP AIR VENT THROUGH DOOR
E	POWDER	2'-6"	6'-8"								
F	POWDER	2'-6"	6'-8"					FR		T	EXTERIOR GRADE
G	BATH 2	2'-6"	6'-8"								
H	BEDROOM 3	2'-4"	6'-8"								
I	BEDROOM 3	2'-4"	6'-8"								
J	BEDROOM 3	2'-6"	6'-8"								
K	BEDROOM 1	2'-6"	6'-8"								
L	BEDROOM 1	2'-6"	6'-8"								
M	BEDROOM 1	6'-0"	6'-8"					BP			
N	BATH 1	2'-6"	6'-8"								

KEY: VERIFY DOOR SIZES BEFORE PLACING ORDER

BP	BI-PASS	T	TEMPERED/SAFETY GLASS
BF	BI-FOLD	OS	OVERHEAD SECTIONAL
SC	SOLID CORE	O	OBSCURE
HC	HOLLOW CORE	E	EXISTING TO REMAIN
1HR	1HR RATED FIRE DOOR W/SELF CLOSING HINGES	FR	FRENCH DOOR
SL	SLIDER		
SGD	SLIDING GLASS DOOR		

Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
①	PLAN REVIEW COMMENTS
②	PLAN REVIEW COMMENTS




REMODEL & ADDITION

OWNER:


Drawing By:
Chris Klimen
klimen@att.net
PH: 510.928.1359

Peter Christopher Klimen
DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL: KLIMEN@ATT.NET DATE: 00/00/00


DOOR & WINDOW SCHEDULE




(E) ELEVATION FROM WEST
SCALE: 1/4"=1'-0"




(E) ELEVATION FROM SOUTH
SCALE: 1/4"=1'-0"




(E) ELEVATION FROM EAST
SCALE: 1/4"=1'-0"



(N) ELEVATION FROM WEST
SCALE: 1/4"=1'-0"



(N) ELEVATION FROM SOUTH
SCALE: 1/4"=1'-0"



(N) ELEVATION FROM EAST
SCALE: 1/4"=1'-0"

Revision History

	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:

Drawing By:

Chris Klimen

klimen@att.net

PH: 510.928.1359

Peter Christopher Klimen

DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL:KLIMEN@ATT.NET DATE: 00/00/00

ELEVATIONS

A2.1

Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS


REMODEL & ADDITION

OWNER:


Drawing By:
 Chris Klimen
 klimen@att.net
 PH: 510.928.1359
 Peter Christopher Klimen
DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
 EMAIL: KLIMEN@ATT.NET DATE: 00/00/00

**CARPORT
 ELEVATIONS**


A2.2




1 ELEVATION FROM WEST
 A2.2 SCALE: 1/2"=1'-0"




2 ELEVATION FROM SOUTH
 A2.2 SCALE: 1/2"=1'-0"



3 ELEVATION FROM EAST
 A2.2 SCALE: 1/2"=1'-0"




4 ELEVATION FROM NORTH
 A2.2 SCALE: 1/2"=1'-0"



(E) 100A MAIN SERVICE PANEL
(N) SUB PANEL

(N) DISCONNECT FOR FAN COIL

- 4" OR 6" LED RECESSED LIGHTING. VERIFY SIZE WITH OWNER. USE FIXTURES SUITABLE FOR DAMP LOCATION IN BATHROOM
- Ⓜ (N) FIRE ALARM. NEW FIRE ALARMS TO BE INTERCONNECTED. SMOKE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING PROVIDED THAT SUCH WIRING IS SERVED FROM A COMMERCIAL SOURCE AND SHALL BE EQUIPPED WITH A BATTERY BACKUP. SMOKE ALARMS WITH INTEGRAL STROBES THAT ARE NOT EQUIPPED WITH BATTERY BACKUP SHALL BE CONNECTED TO AN EMERGENCY ELECTRICAL SYSTEM. SMOKE ALARMS SHALL EMIT A SIGNAL WHEN THE BATTERIES ARE LOW. WIRING SHALL BE PERMANENT AND WITHOUT A DISCONNECTING SWITCH OTHER THAN AS REQUIRED FOR OVERCURRENT PROTECTION.
- Ⓜ (N) CARBON MONOXIDE ALARM. CARBON MONOXIDE ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING WHERE SUCH WIRING IS SERVED FROM A COMMERCIAL SOURCE AND, WHERE PRIMARY POWER IS INTERRUPTED, SHALL RECEIVE POWER FROM A BATTERY. WIRING SHALL BE PERMANENT AND WITHOUT A DISCONNECTING SWITCH OTHER THAN THOSE REQUIRED FOR OVERCURRENT PROTECTION. COMBINATION CARBON MONOXIDE AND SMOKE ALARMS SHALL BE PERMITTED TO BE USED IN LIEU OF CARBON MONOXIDE ALARMS.



- ELECTRICAL NOTES:**
- SEE SHEETS A0.2, G1.0 & G1.1 FOR MANDATORY ELECTRICAL REQUIREMENTS AND SPECIFICATIONS
 - INSTALL SWITCHES @ 45" TO CENTER FROM FINISHED FLOOR U.O.N.
 - INSTALL RECEPTACLES @ 13" TO CENTER FROM FINISHED FLOOR U.O.N.
 - INSTALL SWITCHES & RECEPTACLES @ COUNTER SURFACES @ 8" TO CENTER FROM SURFACE U.O.N.
 - RECEPTACLES ON KITCHEN ISLAND TO BE INSTALLED @ 32" TO CENTER OF RECEPTACLE FROM FINISHED FLOOR
 - INSTALL RECEPTACLES BEHIND RANGE, REFRIGERATOR, WASHER/DRYER, FURNACE, UNDER SINK & ADJACENT TO WATER HEATER @ MANUFACTURERS SUGGESTED LOCATION & ELEVATION
 - INSTALL RECEPTACLES AT LOCATIONS SPECIFIED BY OWNER AND PER CODE REQUIRED SPACING
 - WR = WEATHER RESISTANT

(N) ELECTRICAL PLAN
SCALE: 3/8"=1'-0"

Revision History	
	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

REMODEL & ADDITION


OWNER:

Drawing By:
Chris Klimen
klimen@att.net
PH: 510.928.1359

Peter Christopher Klimen
DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL: KLIMEN@ATT.NET DATE: 00/00/00

ELECTRICAL PLAN

E1.1




CONNECT WATER TO EXISTING HOSE BIBS

CONNECT TO EXISTING WATER SERVICE

(N) 3/4\"/>

(N) WATER SUPPLY
SCALE: 1/4"=1'-0"



PLUMBING NOTES:

- SEE SHEETS A0.2, G1.0 & G1.1 FOR MANDATORY PLUMBING REQUIREMENTS AND FIXTURE SPECIFICATIONS
- PER CAL GREEN REQUIREMENTS: ALL NEW & EXISTING PLUMBING FIXTURES MUST MEET WATER CONSERVING FLOW RATES MANDATED ON SHEET G1.0. ALL EXISTING NON-COMPLIANT FIXTURES THAT ARE NOT REMOVED MUST BE REPLACED.

(N) WASTE & VENT
SCALE: 1/4"=1'-0"

Revision History

	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:

Drawing By:

Chris Klimen

klimen@att.net


PH: 510.928.1359

Peter Christopher Klimen

DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL: KLIMEN@ATT.NET DATE: 00/00/00

**WASTE, VENT,
& SUPPLY
PLAN**


P1.1



MECHANICAL NOTES:

- SEE SHEETS A0.2, G1.0 & G1.1 FOR MANDATORY MECHANICAL REQUIREMENTS AND SPECIFICATIONS
- (N) EXHAUST FANS SHALL BE ENERGY STAR COMPLIANT AND BE DUCTED TO TERMINATE OUTSIDE THE BUILDING. FAN MUST BE CONTROLLED BY A HUMIDITY CONTROL. HUMIDITY CONTROL SHALL BE CAPABLE OF ADJUSTMENT BETWEEN A RELATIVE HUMIDITY RANGE LESS THAN OR EQUAL TO 50% TO A MAXIMUM OF 80%. HUMIDITY CONTROL MAY UTILIZE MANUAL OR AUTOMATIC MEANS OF ADJUSTMENT. HUMIDITY CONTROL MAY BE A SEPARATE COMPONENT TO THE EXHAUST FAN AND IS NOT REQUIRED TO BE INTEGRAL (I.E., BUILT-IN)
- (N) CLOTHES DRYER VENT CMC 504.4 & 502.2.1: A CLOTHES DRYER EXHAUST DUCT SHALL NOT BE CONNECTED TO A VENT CONNECTOR, GAS VENT, CHIMNEY, AND SHALL NOT TERMINATE INTO A CRAWL SPACE, ATTIC, OR OTHER CONCEALED SPACE. EXHAUST DUCTS SHALL NOT BE ASSEMBLED WITH SCREWS OR OTHER FASTENING MEANS THAT EXTEND INTO THE DUCT AND THAT ARE CAPABLE OF CATCHING LINT, AND THAT REDUCE THE EFFICIENCY OF THE EXHAUST SYSTEM. EXHAUST DUCTS SHALL BE CONSTRUCTED OF RIGID METALLIC MATERIAL. TRANSITION DUCTS USED TO CONNECT THE DRYER TO THE EXHAUST DUCT SHALL BE LISTED FOR THAT APPLICATION OR INSTALLED IN ACCORDANCE WITH THE CLOTHES DRYER MANUFACTURER'S INSTALLATION INSTRUCTIONS. CLOTHES DRYER EXHAUST DUCTS SHALL TERMINATE TO THE OUTSIDE OF THE BUILDING NOT LESS THAN 3 FEET FROM A PROPERTY LINE, 10 FEET FROM A FORCED AIR INLET, AND 3 FEET FROM OPENINGS INTO THE BUILDING. AND SHALL BE EQUIPPED WITH A BACKDRAFT DAMPER. SCREENS SHALL NOT BE INSTALLED AT THE DUCT TERMINATION. DEVICES, SUCH AS FIRE OR SMOKE DAMPERS, THAT WILL OBSTRUCT THE FLOW OF THE EXHAUST SHALL NOT BE USED. WHERE JOINING OF DUCTS, THE MALE END SHALL BE INSERTED IN THE DIRECTION OF AIRFLOW. ENVIRONMENTAL EXHAUST DUCTS SHALL NOT DISCHARGE ONTO A PUBLIC WALKWAY.
- DURING CONSTRUCTION, ALL NEW OR EXISTING DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED WITH TAPE, PLASTIC, SHEET METAL OR OTHER METHODS ACCEPTABLE TO THE ENFORCING AGENCY TO REDUCE THE AMOUNT OF WATER, DUST OR DEBRIS WHICH MAY ENTER THE SYSTEM.

(N) MECHANICAL PLAN
SCALE: 1/4"=1'-0"



GAS PIPE SIZING - SCH 40 STEEL PER CPC TABLE 1216.2(1).					
MARK	APPLIANCE	BTU'S	CU FT/HR (BTU/1100)	PIPE LENGTH TO MARK IN LF	REQUIRED PIPE SIZE IN INCHES
A	RANGE	65,000	59	27	1/2
B	FURNACE	100,000	90	41	3/4
C	CLOTHES DRYER	35,000	32	50	1/2
D	WATER HEATER - INSTANT	285,000	259	29	1
B + C	--	--	122	50	3/4
A + B + C	--	--	181	50	1

GAS LOADS DERIVED FROM CPC TABLE 1208.4.1

(N) GAS PLAN
SCALE: 1/4"=1'-0"

Revision History

	AS-BUILT
	PRELIMINARY DESIGN
	DESIGN
	PERMIT SET
▲	PLAN REVIEW COMMENTS
▲	PLAN REVIEW COMMENTS

REMODEL & ADDITION

OWNER:

Drawing By:

Chris Klimen

klimen@att.net

PH: 510.928.1359

Peter Christopher Klimen

DIGITALLY SIGNED BY PETER CHRISTOPHER KLIMEN
EMAIL:KLIMEN@ATT.NET DATE: 00/00/00

GAS &
MECHANICAL
PLANS

P1.2 &
M1.1